**Attic Finish with Owners Suite** 

Address:

City, State, Zip:

Phone:

**Email:** 



## **BUDGET ANALYSIS**

Project Description: Date: 6/9/2022

Convert an unfinished attic space to a 25' x 15' finished room, closet, and a 5' x 7' bathroom with a tub/tiled shower, luxury vinyl floor and updated classic fixtures. Includes insulation and two new windows. Unfinished/unconditioned storage space under the eaves. All walls will be finished, trim will be painted and flooring to be carpeted. Stairs will remain but will get a rail and balusters around the stairwell. Mechanicals to include HVAC extended into the new space, electrical wiring and lighting to code and plumbing for new bathroom. No upgrade or replacement of furnace. Foam insulation ceiling and exterior walls. Existing insulation in floor joists of unfinished space. Accessories by Owner. Includes all painting and staining.

	Qty. Unit	Low I	Budget	High l	Budget
01. Permits and Design					
Permit	1 EA	\$	2,442.50	\$	2,808.88
Design and Planning Process See Design and Planning Agreement for Details.	1 EA	\$	6,600.00	\$	6,600.00
Storight and I takening 1 to to Storight and I takening 1 ignormality so States	1 2.1		0,000.00		0,000.00
Subtotal - Category 1		\$	9,042.50	\$	9,408.88
2. Site Prep and Demolition					
Site Prep Small to Medium Project (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.	1 EA	\$	446.55	\$	513.53
Demolition of work area to EPA lead safe work practices. Expects demolition to existing space is minimal/this is mostly an unfinished space.	1 EA	\$	705.60	\$	811.44
Option: If needed, removal of vermiculite insulation in attic. Additional cost if needed.	0 OPT	\$	0.00	\$	0.00
Option: Charge to test flooring, pipes, duct work for asbestos. Add \$98.00 if needed.	0 OPT	\$	0.00	\$	0.00
Furnish active air filtration on the site for the duration of the project to minimize dust and	1 EA	\$	150.70	\$	173.31
particulate infiltration in non-construction areas.					
NOTE: Although care is taken to carefully remove materials from wall and floor surfaces, screw pops, hairline cracks, and other issues can occassionally arise in adjacent spaces. No costs are included in this estimate to patch drywall or plaster or repaint walls in adjacent spaces but the need could arise and can be handled with a Change Order. We also use the most expensive and sensitive tape when taping prep to the floor, walls, or trim. If it is a bad or old finish, there is a small chance that it may peel some of the existing finish off. Any additional repairs will be an additional charge and dealt with via Change Order.	1 Note	\$	0.00	\$	0.00
Subtotal - Category 2		\$	1,302.85	\$	1,498.28
3. Landscaping and Fence - By Field Outdoor Spaces or homeowner					
Subtotal - Category 3  4. Concrete and Foundation		\$	-	\$	-
Subtotal - Category 4		8		S	
95. Masonry		3		J	-
Subtotal - Category 5		\$	_	\$	-
6. Framing					
Patch in subfloor as needed for mechanical rough-ins	64 SF	\$	592.80	\$	681.72
Basic interior wall framing: Flatten walls and ceiling, fur out as needed, furnish and install backers for rock and accessories	1 EA	\$	367.80	\$	422.97

2x2 Fur wall and/or ceiling framing (materials and labor) Basement or Attic interior wall framing (materials and labor)	410 SF 110 LF	\$ \$	1,830.86 5,082.33	\$ \$	2,105.4 5,844.6
total - Category 6		\$	7,873.79	\$	9,054.8
Roofing, Flashing, Gutters					
total - Category 9		\$	-	\$	-
Exterior Trim, Porches and Decks					
ototal - Category 10		\$	-	\$	-
Siding, Soffit, and Fascia					
total - Category 11		\$	-	\$	-
Exterior Doors and Trim					
ototal - Category 12		\$	-	\$	-
Windows					
Furnish and install new custom size clad/wood pocket insert window;	2 EA	\$	2,871.00	\$	3,301.6
Window allowance \$900.00/ea.					
Manufacturer:					
Line:					
Operation type, size, jamb, tempering, egress notes: see plan/schedule					
Exterior material /color:					
Interior material /color:					
Glass: clear Low E2 w/ Argon is standard- modify if something else desired					
Grids (type, size, pattern, color):					
Interior weather Strip color: ???					
Hardware type/color:					
WOCD: Y or N (and specifiy color, if diff. from hardware)					
Screen surround material/color:					
Screen color:					
Stop description:					
Window install material (flashing, caulk, shims, etc.)	2 EA	\$	125.00	\$	143.7
ototal - Category 13		\$	2,996.00	\$	3,445.4
			-,-,-	Ψ.	٠,٠.٠٠
Plumbing  NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them.  The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no	1 Note	\$	0.00	\$	·
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.	1 Note				0.0
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or	1 Note				·
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.		\$	0.00	\$	0.0
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or	1 Note				·
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.		\$	0.00 343.75	\$	395
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note:  Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit	1 EA	\$	0.00	\$	395
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet;	1 EA	\$	0.00 343.75	\$	395
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.	1 EA	\$	0.00 343.75	\$	395
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer:	1 EA	\$	0.00 343.75	\$	395
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #:	1 EA	\$	0.00 343.75	\$	0. 395. 880.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish:	1 EA 1 EA	\$ \$	0.00 343.75 765.85	\$ \$ \$	0. 395. 880.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea. Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub;	1 EA 1 EA	\$ \$	0.00 343.75 765.85	\$ \$ \$	0. 395. 880.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.	1 EA 1 EA	\$ \$	0.00 343.75 765.85	\$ \$ \$	0. 395. 880.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish:  Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side:	1 EA 1 EA	\$ \$	0.00 343.75 765.85	\$ \$ \$	0. 395. 880.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea. Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea. Drain side: Manufacturer:	1 EA 1 EA	\$ \$	0.00 343.75 765.85	\$ \$ \$	395 880.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish:  Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish:	1 EA 1 EA 1 EA	\$ \$ \$	0.00 343.75 765.85 1,952.65	\$ \$ \$	395 880.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish:  Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish:  Furnish and install tub waste and overflow	1 EA 1 EA	\$ \$	0.00 343.75 765.85	\$ \$ \$	0. 395. 880. 2,245.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish:  Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish:  Furnish and install tub waste and overflow Model #:	1 EA 1 EA 1 EA	\$ \$ \$	0.00 343.75 765.85 1,952.65	\$ \$ \$	0. 395. 880. 2,245.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish:  Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish:  Furnish and install tub waste and overflow Model #: Finish:	1 EA 1 EA 1 EA	\$ \$ \$ \$	0.00 343.75 765.85 1,952.65	\$ \$ \$	0. 395. 880. 2,245.
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish: Furnish and install tub waste and overflow Model #: Finish: Furnish and install tub filler faucet, valve, trim, and rough-in valve;	1 EA 1 EA 1 EA	\$ \$ \$	0.00 343.75 765.85 1,952.65	\$ \$ \$	395 880. 2,245
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer:  Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish: Furnish and install tub waste and overflow Model #: Finish: Furnish and install tub filler faucet, valve, trim, and rough-in valve; Tub Filler faucet package allowance \$300.00	1 EA 1 EA 1 EA	\$ \$ \$ \$	0.00 343.75 765.85 1,952.65	\$ \$ \$	395 880. 2,245
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish: Furnish and install tub waste and overflow Model #: Finish: Furnish and install tub filler faucet, valve, trim, and rough-in valve; Tub Filler faucet package allowance \$300.00  Manufacturer:	1 EA 1 EA 1 EA	\$ \$ \$ \$	0.00 343.75 765.85 1,952.65	\$ \$ \$	395 880. 2,245
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish: Furnish and install tub waste and overflow Model #: Finish: Furnish and install tub filler faucet, valve, trim, and rough-in valve; Tub Filler faucet package allowance \$300.00 Manufacturer: Model #:	1 EA 1 EA 1 EA	\$ \$ \$ \$	0.00 343.75 765.85 1,952.65	\$ \$ \$	395 880. 2,245
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish: Furnish and install tub waste and overflow Model #: Finish: Furnish and install tub filler faucet, valve, trim, and rough-in valve; Tub Filler faucet package allowance \$300.00  Manufacturer:	1 EA 1 EA 1 EA	\$ \$ \$ \$	0.00 343.75 765.85 1,952.65	\$ \$ \$	395 880. 2,245
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish: Furnish and install tub waste and overflow Model #: Finish: Furnish and install tub filler faucet, valve, trim, and rough-in valve; Tub Filler faucet package allowance \$300.00 Manufacturer: Model #:	1 EA 1 EA 1 EA	\$ \$ \$ \$	0.00 343.75 765.85 1,952.65	\$ \$ \$	0.0
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish:  Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side:  Manufacturer: Model #: Finish:  Furnish and install tub waste and overflow Model #: Finish:  Furnish and install tub filler faucet, valve, trim, and rough-in valve; Tub Filler faucet package allowance \$300.00  Manufacturer: Model #: Finish:	1 EA 1 EA 1 EA 1 EA	\$ \$ \$ \$	0.00 343.75 765.85 1,952.65 272.71	\$ \$ \$ \$	395 880 2,245 313 1,067
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish:  Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish:  Furnish and install tub waste and overflow Model #: Finish:  Furnish and install tub filler faucet, valve, trim, and rough-in valve; Tub Filler faucet package allowance \$300.00  Manufacturer: Model #: Finish: Furnish and install toilet;	1 EA 1 EA 1 EA 1 EA	\$ \$ \$ \$	0.00 343.75 765.85 1,952.65 272.71	\$ \$ \$ \$	395.3 880.7 2,245.3
NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish:  Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #: Finish:  Furnish and install tub waste and overflow Model #: Finish:  Furnish and install tub filler faucet, valve, trim, and rough-in valve; Tub Filler faucet package allowance \$300.00  Manufacturer: Model #: Finish:  Furnish and install toilet; Toilet allowance \$300.00/ea.	1 EA 1 EA 1 EA 1 EA	\$ \$ \$ \$	0.00 343.75 765.85 1,952.65 272.71	\$ \$ \$ \$	395 880 2,245 313 1,067

New attic or 2nd floor bathroom rough-in	1 EA	\$	5,000.00	\$	5,750.00
Install a new roof jack on new plumbing vent penetrations.	1 EA	\$	384.05	\$	441.66
ubtotal - Category 14		\$	10,413.24	\$	11,975.22
5. HVAC	1.54		212.50	Φ.	250.20
Mechanical permit  Install new bathroom vent fan and vent to the exterior.	1 EA 1 EA	\$	312.50 875.00	\$	359.38
Relocate supply air or return air vent	4 EA	\$ \$	2,200.00	\$ \$	1,006.25 2,530.00
Furnish and install ducted mini split heat pump and cooling system, best used for multiple	1 EA	\$	7,562.50	\$	2,530.00 8,696.88
rooms, requires ducting but doesn't need gas or venting. (units are rectangular and usually hung	1 211	T T	7,502.50	Ψ	0,070.00
from ceiling).					
Based on a small run with 3-4 vents, central return, 1 or 2 rooms.					
ubtotal - Category 15		\$	10,950.00	\$	12,592.50
6. Electrical		J.	10,750.00	J.	12,372.30
Electrical Permit	1 EA	\$	231.25	\$	265.94
Specify device color:	1 EA	\$	0.00	\$	0.00
White, light almond, or ivory are standard. PICK ONE					
Specify switch style					
Pole or Decora. PICK ONE					
Bathroom price for electrical (Includes GFCI Outlet to code, new switches and wiring in bath,	1 EA	\$	1,875.00	\$	2,156.25
and Lutron push button timer switch for the bath fan).					
NOTE: Battery operated smoke detector and CO by homeowner. Will all need to be	1 Note	\$	0.00	\$	0.00
functional and placed per code. Code requires each floor have one smoke detector. In					
addition, any bedroom needs a smoke detector. Also there must be a carbon monoxide detector within 10 feet of each bedroom. **If the rest of the home does not meet the above					
code, homeowner will be responsible to update or if homeowner prefers, Castle will perform					
updates and a change order will be issued**"					
NOTE: No wiring for security, doorbell, TV, speakers or phone is included in pricing. If	1 Note	\$	0.00	\$	0.00
any low voltage wires are found in a wall being opened up, additional costs to re-route them will occur.					
	2.54		1 020 00		1 172 00
CBR furnish and elec install light fixture; Fixture allowance \$150.00/ea.	3 EA	\$	1,020.00	\$	1,173.00
Manufacturer:					
Model #:					
Finish:					
NOTE: For all home owner provided fixtures, there may be additional install costs for more	1 Note	\$	0.00	\$	0.00
complicated fixtures. ALL light fixtures must be specified prior to contract signing and be UL listed to pass inspection. All material issues related to materials supplied by owner are					
the responsibility of the owner to resolve. Extra trade partner trip charges may apply for					
return visits if material issues can not be resolved in timely manner.					
CBR furnish, HVAC install, and Elec wire bath fan:	1 EA	\$	313.78	\$	360.84
Panasonic, • FV-0510VS1 Whisper Value 50/80/100 CFM Low Profile, 0.3-1.3 sones, 3 3/8" Housing Depth - UL listed for wall and ceiling installation, Energy Star Qualified - DC Fan					
Motor					
See hvac for install/venting.					
Finished attic price for electrical	335 SF	\$	4,396.88	\$	5,056.41
ubtotal - Category 16		\$	7,836.90	\$	9,012.44
<b>7. Insulation</b> R-21 Insulation batts with poly	490 SF	\$	918.75	\$	1,056.56
1-1/2 Story houses sloped ceilings 5" spray foam insulation; Please note - spray foam insulation	1152 SF	\$	12,816.00	\$	14,738.40
requires people and pets to vacate the home for 24 hours while the insulation is curing		ľ	,	,	,
ubtotal - Category 17		\$	13,734.75	\$	15,794.96
8. Drywall					
Furnish and install 1/2" or 5/8" drywall on ceilings with smooth finish	652 SF	\$	4,075.00	\$	4,686.25
Furnish and install 1/2" drywall on walls with smooth finish	740 SF	\$	4,440.00	\$	5,106.00
		1	1 0 42 77	\$	2,120.31
Install drywall in attic crawl space to cover up spray foam per code - Fire taped only	500 SF	\$	1,843.75	Φ	2,120.31
Install drywall in attic crawl space to cover up spray foam per code - Fire taped only Boom/cartage fee for 2nd floor and basements	500 SF 1 EA	\$ \$	331.25	\$	380.94

19. Tile and Stone Install kerdi board tile backer. Standard for shower or wet walls.	70 SF	\$	592.70	\$	681.61
Install large format tile on shower surround walls using spacers.  Tile allowance: \$4.50/SF	70 SF	\$	3,136.07	\$	3,606.48
Supplier: Spec#/description:					
Furnish and install bullnose tile, pattern TBD; <u>Tile allowance \$4.50/LF</u> <u>Supplier:</u>	13 LF	\$	199.45	\$	229.37
Spec#/description:					
GROUT - 10# Tec Power Grout Color:	1 EA	\$	34.76	\$	39.98
Stock Material Costs - Denshield, Mud, Self Leveler, Mastic, Thinset, Redguard, Tape, Caulk, Sponges, Silicone, etc. <b>Include on all Tile projects.</b>	1 EA	\$	420.29	\$	483.34
Subtotal - Category 19		\$	4,383.28	\$	5,040.77
20. Millwork, Doors, Hardware	100 77		2.425.02	Φ.	2 500 01
Classic base molding - NOTE - Assumes 1X and top cap  Species: 1X size:	120 LF	\$	2,425.92	\$	2,789.81
Top cap profile and height #:					
Brand/profile #:  Classic window and door casing - NOTE: Assumes 1X with a backband and a sill and stool on the windows	140 LF	\$	2,567.74	\$	2,952.90
Species: Overall size: 1X size:					
Backband brand/profile#:  "Picture framed": Y or N					
Stool detail (thickness/extention) and apron detail (height, profile #):					
Furnish and install wood jambs to an opening  NOTE: The casing for the opening is on the window/door casing line  Species:	20 LF	\$	399.18	\$	459.06
Jamb depth: Opening size:					
Furnish and install a pre-hung door  Hinge finish:	1 EA	\$	659.25	\$	758.14
Species:					
Style: Brand/model#:					
Core: solid or hollow					
Furnish and install a bi-pass door. Figured PER slab. See jamb/stop line above.	2 EA	\$	1,158.00	\$	1,331.70
Jamb: wood or sheetrock opening Species: Style:					
Brand/model #:					
Core: solid or hollow					
Furnish and install door knob/handle hardware Allowance: \$30.00	3 EA	\$	225.84	\$	259.72
Manufacturer/model #: Style (locking, passage, etc.): Finish:					
Furnish and install door stan	2 EA	•	22.64	•	27.54
Furnish and install door stop  Allowance: \$5.00	2 EA	\$	32.64	\$	37.54
Manufacturer/model #:					
Style (wall mount, hinge mount, etc.): Finish:					

feight: precies: prand/model#:  formal: precies: prand: precies: formal: precies: pr	F S	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	2,131.20 338.78 426.75 10,926.57	\$ \$ \$ \$	2,450 389 490 12,569
Parad/model#:  Paramal: Parama	F S	\$ \$ \$	338.78 426.75 10,926.57 58.67	\$ \$ \$	490 12,569
Furnish and install railing. Includes top rail, bottom rail, and spindles 4.5" O.C.  Forand:	F S	\$ \$ \$	338.78 426.75 10,926.57 58.67	\$ \$ \$	490 12,569
Brand: species: Sottom rail style/profile #: Bottom rail style/spee #: Bottom rail	F S	\$ \$ \$	338.78 426.75 10,926.57 58.67	\$ \$ \$	490 12,569
Species:  Op rail style/profile #:  Spindle (balustrades)  Spindle (balustra	F :	\$ \$	426.75 10,926.57 58.67	\$ \$	490 12,569
For pail style/profile #: Soutom rail style/profile #: Soutom rail style/profile #: Sipindle (balustrades) style/profile #: Sipindle (balustrades) style/profile #: Sipindle (balustrades) style/profile #: Sumish and install basic grippable handrail with mounting hardware  In the siping of the sip	F :	\$ \$	426.75 10,926.57 58.67	\$ \$	490 12,569
Bottom rail style/profile #: spindle (balustrades) style/profile #: ididitional detail/profile #s  Additional detail/profile #s: ididitional detail/profile	F :	\$ \$	426.75 10,926.57 58.67	\$ \$	12,56s
ipindle (balustrades) style/profile #:  illet (Y or N)profile #:  dditional detail/profile #s:  irumish and install basic grippable handrail with mounting hardware  Brand/profile #:  ipiccies:  lardware style/spec #:  lardware style/spec #:  lardware finish:  irumish and install closet rod and white melamine shelf.  10 L  - Category 20  letry, Countertops and Appliances  (snobs and pulls will be installed on all cabinet doors and drawers.  landufacturer:  izic:  dodel #:  inish:  CABINET SPECS:  Pabinet Line: Crystal Current or Crystal Keyline  Box Type: Frameless, Framed, Inset  Door Construction: MDF or Wood  Door Style:  Door Style:  Drawer Style: 5 piece or slab  Drawer box construction: Interior material: select one- natural melamine on particle board  ubstrate standard or natural basswood vener on plywood substrate upgrade, white melamine on barticle board substrate option for current frameless, or all plywood green core box with natural naple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  inish: paint or stain  Dolor:  sheen:  ipiccialties: (distressing, highlights, etc.)  Trown:  shoe: Yes  inished end: Furniture groove finished end (standard) or optional upgrade to flush finished any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included.  Any apcessories will be noted on plan. If accessory provided by Castle and not Cabinet	F :	\$ \$	426.75 10,926.57 58.67	\$ \$	490 12,569
intervention of the content of the c	F :	\$ \$	426.75 10,926.57 58.67	\$ \$	12,56s
Additional detail/profile #s:  Turnish and install basic grippable handrail with mounting hardware  Brand/profile #:  Species:  Hardware style/spec #:  Hardware finish:  Turnish and install closet rod and white melamine shelf.  Category 20  Hetry, Countertops and Appliances  Knobs and pulls will be installed on all cabinet doors and drawers.  Another the style of the	F :	\$ \$	426.75 10,926.57 58.67	\$ \$	12,56s
furnish and install basic grippable handrail with mounting hardware furnish profile #:  pr	F :	\$ \$	426.75 10,926.57 58.67	\$ \$	12,56 6
Brand/profile #: species: Hardware style/spec #: Hardware finish:  Furnish and install closet rod and white melamine shelf.  Category 20  Retry, Countertops and Appliances  Knobs and pulls will be installed on all cabinet doors and drawers.  Milowance: \$7.00/ea.  Manufacturer:  Size:  Model #:  Finish:  CaBINET SPECS:  Cabinet Line: Crystal Current or Crystal Keyline  Box Type: Frameless, Framed, Inset  Door Construction: MDF or Wood  Door Style:  Drawer box construction: Interior material: select one- natural melamine on particle board  substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on  sarticle board substrate option for current frameless, or all plywood green core box with natural  naple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  "inish: paint or stain  Color:  theen:  Specialties: (distressing, highlights, etc.)  Crown:  Shoe: Yes  "inished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on  trawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	F :	\$ \$	426.75 10,926.57 58.67	\$ \$	12,56 6
Adardware style/spec #: Hardware finish:  Lore Category 20  Letry, Countertops and Appliances  Knobs and pulls will be installed on all cabinet doors and drawers.  Allowance: \$7.00/ca.  Annufacturer:  Lize:  Model #:  Linish:  CABINET SPECS:  Cabinet Line: Crystal Current or Crystal Keyline  Box Type: Frameless, Framed, Inset  Door Construction: MDF or Wood  Door Style:  Drawer Style: 5 piece or slab  Drawer byle: 5 piece or slab  Drawer box construction: Interior material: select one- natural melamine on particle board  ubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on  laracticle board substrate option for current frameless, or all plywood green core box with natural  naple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  Linish: paint or stain  Color:  Specialties: (distressing, highlights, etc.)  Crown:  Shoe: Yes  Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished  Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on  larawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	A	\$	<b>10,926.57</b> 58.67	\$	<b>12,56</b>
Jardware style/spec #: Jardware finish:  Jardwar	A	\$	<b>10,926.57</b> 58.67	\$	<b>12,56</b>
Addraware finish:  Furnish and install closet rod and white melamine shelf. 10 L  - Category 20  Letry, Countertops and Appliances  Knobs and pulls will be installed on all cabinet doors and drawers. 4 E  Millowance: \$7.00/ea.  Manufacturer:  Size:  Model #:  Finish:  CABINET SPECS: Cabinet Line: Crystal Current or Crystal Keyline  Box Type: Frameless, Framed, Inset  Door Construction: MDF or Wood  Door Style:  Drawer Style: 5 piece or slab  Drawer box construction: Interior material: select one- natural melamine on particle board  substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on larticle board substrate option for current frameless, or all plywood green core box with natural naple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  Finish: paint or stain  Color:  Scheen:  Specialties: (distressing, highlights, etc.)  Crown:  Scheen:  Specialties: (distressing, highlights, etc.)	A	\$	<b>10,926.57</b> 58.67	\$	<b>12,56</b>
Furnish and install closet rod and white melamine shelf.  10 L  Category 20  Letry, Countertops and Appliances  Chobs and pulls will be installed on all cabinet doors and drawers.  Chobs and pulls will be installed on all cabinet doors and drawers.  Anufacturer:  Size:  Model #:  Finish:  CABINET SPECS: Cabinet Line: Crystal Current or Crystal Keyline Coor Construction: MDF or Wood Coor Style: Crawer Style: 5 piece or slab Crawer box construction: Interior material: select one- natural melamine on particle board cubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  Finish: paint or stain Color:  Schoe: Yes  Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished thay applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on trawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	A	\$	<b>10,926.57</b> 58.67	\$	12,56:
Category 20  Letry, Countertops and Appliances  Chobs and pulls will be installed on all cabinet doors and drawers.  Allowance: \$7.00/ea.  Manufacturer:  Size:  Model #:  Finish:  Cabinet Line: Crystal Current or Crystal Keyline  Box Type: Frameless, Framed, Inset  Door Construction: MDF or Wood  Door Style:  Drawer Style: 5 piece or slab  Drawer box construction: Interior material: select one- natural melamine on particle board  substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  Finish: paint or stain  Color:  Schoe: Yes  Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished way applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on lawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	A	\$	<b>10,926.57</b> 58.67	\$	<b>12,56</b>
Inchery, Countertops and Appliances  Chobs and pulls will be installed on all cabinet doors and drawers.  Allowance: \$7.00/ea.  Manufacturer:  Idea of the Counter of Crystal Current or Crystal Keyline  Box Type: Frameless, Framed, Inset  Door Construction: MDF or Wood  Door Style:  Drawer Style: 5 piece or slab  Drawer box construction: Interior material: select one- natural melamine on particle board  substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural naple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  Inish: paint or stain  Color:  Sheen:  Sheen:  Sheen:  Sheen:  Sheen:  Sheei: (distressing, highlights, etc.)  Crown:  Shoe: Yes  Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished way applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on lawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	A	\$	58.67	\$	6
Annobs and pulls will be installed on all cabinet doors and drawers.  Allowance: \$7.00/ea.  Manufacturer:  Size:  Model #:  Sinish:  CABINET SPECS:  Cabinet Line: Crystal Current or Crystal Keyline  Box Type: Frameless, Framed, Inset  Ooor Construction: MDF or Wood  Ooor Style:  Drawer Style: 5 piece or slab  Drawer box construction: Interior material: select one- natural melamine on particle board  substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural neaple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  Sinish: paint or stain  Color:  Sheen:  Sheen:  Sheen:  Sheen:  Sheen:  Sheei:  Sheei					
Allowance: \$7.00/ea.  Manufacturer:  Size:  Model #:  Sinish:  CABINET SPECS: Cabinet Line: Crystal Current or Crystal Keyline  Box Type: Frameless, Framed, Inset  Door Construction: MDF or Wood  Dorawer Style: 5 piece or slab  Drawer box construction: Interior material: select one- natural melamine on particle board  substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on  particle board substrate option for current frameless, or all plywood green core box with natural  maple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  Sinish: paint or stain  Color:  Sheen:  Sheen:  Sheen:  Sheen:  Sheen:  Sheen:  Sheen:  Shinished end: Furniture groove finished end (standard) or optional upgrade to flush finished  Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on  Jawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Manufacturer:  Size:  Model #:  Sinish:  CABINET SPECS: Cabinet Line: Crystal Current or Crystal Keyline Box Type: Frameless, Framed, Inset Oper Construction: MDF or Wood Oper Style: Orawer Style: 5 piece or slab Orawer box construction: Interior material: select one- natural melamine on particle board ubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural naple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species: Sinish: paint or stain Color: Scheen: Specialties: (distressing, highlights, etc.) Crown: Schoe: Yes Sinished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	A	\$	0.00	\$	
Model #: Finish:  CABINET SPECS: Cabinet Line: Crystal Current or Crystal Keyline Sox Type: Frameless, Framed, Inset Over Construction: MDF or Wood Over Style: Orawer Style: 5 piece or slab Orawer box construction: Interior material: select one- natural melamine on particle board ubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on trawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	A	\$	0.00	\$	
CABINET SPECS: Cabinet Line: Crystal Current or Crystal Keyline Sox Type: Frameless, Framed, Inset Over Construction: MDF or Wood Over Style: Orawer Style: 5 piece or slab Orawer box construction: Interior material: select one- natural melamine on particle board ubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on varticle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans. Wood Species: Vinish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Sinished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on trawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	Α :	\$	0.00	\$	ı
Cabinet SPECS: Cabinet Line: Crystal Current or Crystal Keyline Box Type: Frameless, Framed, Inset Door Construction: MDF or Wood Door Style: Drawer Style: 5 piece or slab Drawer box construction: Interior material: select one- natural melamine on particle board ubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans. Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	A :	\$	0.00	\$	
Cabinet Line: Crystal Current or Crystal Keyline Box Type: Frameless, Framed, Inset Door Construction: MDF or Wood Door Style: Drawer Style: 5 piece or slab Drawer box construction: Interior material: select one- natural melamine on particle board ubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans. Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on lrawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	A :	\$	0.00	\$	
Cabinet Line: Crystal Current or Crystal Keyline Box Type: Frameless, Framed, Inset Door Construction: MDF or Wood Door Style: Drawer Style: 5 piece or slab Drawer box construction: Interior material: select one- natural melamine on particle board ubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans. Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on lrawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet		Ψ	0.00	Ψ	
Box Type: Frameless, Framed, Inset Door Construction: MDF or Wood Door Style: Drawer Style: 5 piece or slab Drawer box construction: Interior material: select one- natural melamine on particle board ubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans. Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on lrawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet				1	
Door Construction: MDF or Wood Door Style: Drawer Style: 5 piece or slab Drawer Style: 5 piece or slab Drawer box construction: Interior material: select one- natural melamine on particle board ubstrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans. Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on lrawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Orawer Style: 5 piece or slab Orawer Style: 5 piece or slab Orawer box construction: Interior material: select one- natural melamine on particle board substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on sarticle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species: Sinish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Sinished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on lawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Orawer box construction: Interior material: select one- natural melamine on particle board substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  Finish: paint or stain  Color:  Sheen:  Specialties: (distressing, highlights, etc.)  Crown:  Shoe: Yes  Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on lrawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species:  Sinish: paint or stain  Color:  Sheen:  Specialties: (distressing, highlights, etc.)  Crown:  Shoe: Yes  Sinished end: Furniture groove finished end (standard) or optional upgrade to flush finished any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
naple veneer if keyline; finished interiors of any cabinets would be noted on plans.  Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on Irawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on Irawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Sinished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Sinished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Sinished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on drawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on larawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on lrawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
drawing, not included.  Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Crystal - Current line: Furnish and install vanity base cabinets - stained or painted wood 4 L					
	F	\$	1,282.80	\$	1,47
6 1 400 G 1: 1 . 11	. 1	•			
Moderate - a 48" Cultured marble countertop with integral sink will be installed. Includes 1 E	A	\$	522.30	\$	60
tandard colors (pure colors, granite, onyx, and elite granite are extra costs)  Color:					
Chickness:					
ntegraded sink/model #:					
Jndermount: Y (see plumbing category) or N					
" Back Splash (Integrated, set on, or NONE):					
" Side Splash (Integrated, set on, or NONE):					
APPLIANCES: 1 M					(
NOTE: Client to communicate with appliance supplier regarding delivery of appliances they	lote	\$	0.00	\$	
ourchased and arrange to meet/receive delivery themselves. The project manager will be in	lote	\$	0.00	\$	
ommunication with client regarding that timing.	lote	\$	0.00	\$	
- Category 21	lote :	\$	0.00	\$	

cialties					
Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. <u>Classic.</u>	1 EA	\$	213.55	\$	245.
Allowance \$60.00. Install included for 3 items.					
Manufacturer:					
Model/spec #:					
Finish color:					
Furnish and install a permanent, screw in shower curtain rod	1 EA	\$	146.72	\$	168
Manufacturer:	1 2.1	ľ	1.0.72	"	100
Model/spec #:					
Finish color:					
Install additional accessories being installed into tile.	2 EA	\$	171.26	\$	196
ıl - Category 22		\$	531.53	\$	611
pring					
Floor prep. Smoothing, leveling, etc.	1 HR	\$	100.00	\$	115
Furnish and install underlayment (based on 1/4" plywood) for vinyl, Marmoleum, cork, or other	25 SF	\$	116.33	\$	133
flooring requiring a smooth underlayment.	25 51	•	110.55	Ψ	130
Floor transitions.	2 EA	\$	188.20	\$	216
Description Description	2 LA	Ψ	100.20	Ψ	210
Type:					
Finish:					
Furnish and install luxury vinyl tile on floor. Mannington Adura FLEX, plank or tile (Non-	25 SF	\$	368.76	\$	424
grouted)	20 101	Ψ	500.70	Ψ	72
Allowance \$4.90 sf		1			
Line/series:					
Color:					
Tile size:					
				١.	
Moderate carpet and pad will be installed.	420 SF	\$	2,887.50	\$	3,320
\$4.50/SF Allowance - Includes carpet AND pad					
Manufacturer:					
Manufacturer: Line/series:					
Manufacturer: Line/series: Color:		<u> </u>	3 660 79	\$	4.209
Manufacturer: Line/series: Color: al - Category 23		\$	3,660.79	\$	4,209
Manufacturer: Line/series: Color: al - Category 23 Inting and Decorating	600 SF				Í
Manufacturer: Line/series: Color: al - Category 23  nting and Decorating Prime and painting ceilings using low VOC Paint.	600 SF	\$	<b>3,660.79</b> 1,162.14	\$	Í
Manufacturer: Line/series: Color: al - Category 23 Inting and Decorating	600 SF				ŕ
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint.  COLOR: Standard flat ceiling white		\$	1,162.14	\$	1,330
Manufacturer: Line/series: Color: al - Category 23 nting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.	600 SF 740 SF				1,330
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer:		\$	1,162.14	\$	1,330
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer: Color name and #:		\$	1,162.14	\$	1,330
Manufacturer: Line/series: Color: al - Category 23 nting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer: Color name and #: Sheen:		\$	1,162.14 949.72	\$	1,336
Manufacturer: Line/series: Color: al - Category 23 nting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for		\$	1,162.14	\$	1,336
Manufacturer: Line/series: Color: al - Category 23 Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood	740 SF	\$	1,162.14 949.72	\$	1,336
Manufacturer: Line/series: Color: al - Category 23 Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.	740 SF	\$	1,162.14 949.72	\$	1,336
Manufacturer: Line/series: Color: al - Category 23 Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able. Manufacturer:	740 SF	\$	1,162.14 949.72	\$	1,336
Manufacturer: Line/series: Color: al - Category 23 Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able. Manufacturer: Color name and #:	740 SF	\$	1,162.14 949.72	\$	1,330
Manufacturer: Line/series: Color: al - Category 23 Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able. Manufacturer:	740 SF	\$	1,162.14 949.72	\$	1,336
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)	740 SF	\$	1,162.14 949.72	\$	1,330 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen:  Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our	740 SF 260 LF	\$ \$	1,162.14 949.72 1,914.90	\$ \$	1,330 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)	740 SF 260 LF	\$ \$	1,162.14 949.72 1,914.90	\$ \$	1,330 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen:  Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to	740 SF 260 LF	\$ \$	1,162.14 949.72 1,914.90	\$ \$	1,336 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.	740 SF 260 LF	\$ \$	1,162.14 949.72 1,914.90	\$ \$	1,336 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able. Manufacturer:	740 SF 260 LF	\$ \$	1,162.14 949.72 1,914.90	\$ \$	1,336 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating  Prime and painting ceilings using low VOC Paint.  COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen:  Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #:	740 SF 260 LF	\$ \$	1,162.14 949.72 1,914.90	\$ \$	1,336 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)	740 SF 260 LF 3 EA	\$ \$ \$	1,162.14 949.72 1,914.90 972.45	s s	1,336 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Priming and painting on interior side of window, one side. NOTE: Our standard is low VOC	740 SF 260 LF	\$ \$	1,162.14 949.72 1,914.90	\$ \$	1,336 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23  Inting and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint. Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able. Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Priming and painting on interior side of window, one side. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood.	740 SF 260 LF 3 EA	\$ \$ \$	1,162.14 949.72 1,914.90 972.45	s s	1,336 1,092 2,202
Manufacturer: Line/series: Color: all - Category 23 mining and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Priming and painting on interior side of window, one side. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.	740 SF 260 LF 3 EA	\$ \$ \$	1,162.14 949.72 1,914.90 972.45	s s	1,336 1,092 2,202
Manufacturer: Line/series: Color: al - Category 23 mining and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition-tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to existing stain/wood condition-tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Priming and painting on interior side of window, one side. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition-tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)	740 SF 260 LF 3 EA	\$ \$ \$	1,162.14 949.72 1,914.90 972.45	s s	1,336 1,092 2,202
Manufacturer: Line/series: Color: all - Category 23 mining and Decorating Prime and painting ceilings using low VOC Paint. COLOR: Standard flat ceiling white  Prime and paint walls using low VOC Paint.  Manufacturer: Color name and #: Sheen: Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Staining and finishing of a door both sides. Includes the jamb of the unit. NOTE: Our standard is low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)  Priming and painting on interior side of window, one side. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.	740 SF 260 LF 3 EA	\$ \$ \$	1,162.14 949.72 1,914.90 972.45	s s	4,209 1,336 1,092 2,202 1,118

NOTE: Please note that when the homeowner is doing the painting, they are responsible for caulking, filling nail holes, and repairing minor wall and ceiling dings. There will need to be a few rounds of touch-ups, due to the nature of construction, and that falls under the scope of the painter.	1 Note	\$	0.00	\$	0.00
Subtotal - Category 24		\$	5,779.81	S	6,646.78
25. Clean Up and Debris Removal		<b>—</b>	5,777.01	Ψ	0,010.70
Disposal and clean-up - remove all site prep, wipe down and broom sweep area. Haul all extra material off site.	1 EA	\$	673.96	\$	775.05
St. Paul Daily street use permit for dumpster - Charged per day. <u>Day 1-30 = \$8/day</u> . <u>Days 31-120 = \$10/day</u> . <u>Weekends count too</u> . If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.	90 Day	\$	720.00	\$	720.00
ADD number of days, dumpster is estimated to be needed over 30 days	60 DAYS	\$	420.00	\$	420.00
20 Yard roll-off dumpster - 10 ton maximum <b>NOTE:</b> for 30 days only. Use line above for estimated days over 30 days	1 EA	\$	418.75	\$	481.56
Regular portable restroom (one month)  NOTE: This cost can be saved if home owner is ok with making a bathroom in the house available to Castle and it's trade partners	3 EA	\$	637.50	\$	733.13
Subtotal - Category 25		\$	2,870.21	\$	3,129.74
Project Subtotal		\$	105,140.98	\$	119,423.38
26. Designer Oversight & Project Management		\$	11,486.65	\$	13,209.65
27. Overhead and Profit		\$	16,480.85	\$	18,952.98
Grand Total**		\$	133,108.48	\$	153,074.75
MN License # BC005657  **Important Notice**  **This is only a ballpark guesstimate. This does not represent actual p best guess based on Castle's past experiences. There are still many unl can affect pricing at this point.	•				
Check or Cash Discount Low 2.5%*  3,327.71 Check or Cash Discount High 2.5%*	\$ 3,826.87	\$	129,780.77	\$	149,247.88

<sup>\*</sup>Doesn't Apply to Bank Financing or loan process that requires Castle to receive payment directly from that entity after Castle has paid subcontractors and secured lien waivers. In these instances Castle essentially acts as

## **Custom Design Showrooms**

Showroom maps & hours can be found on our website at www.CASTLEBRI.com



Minneapolis, MN 55419 P) 612-789-8509



2600 Johnson St. NE Minneapolis, MN 55418 P) 612-789-8509



362 Snelling Ave S. St. Paul, MN 55105 P) 651-699-4164



4020 Minnehaha Ave Minneapolis, MN 55406 P) P) 612-789-8509



## Need Help with Financing Options?









https://www.castlebri.com/financing-options/

## **Castle Offers Financing**



Find out if you qualify

Call or email Tambra Heine, Financial Controller at 612.877.8374 or Tambra@castlebri.com to schedule your 10 minute no obligation consultation.