

**Basement, Bath, and Laundry**

**Address:**

**City, State, Zip:**

**Phone:**

**Email:**



**BUDGET ANALYSIS**

**Project Description:**

**Date: 6/7/2022**

Finishing 850 SF of basement with 9' ceilings, a bathroom, laundry room, craft room, wet bar, bedroom and living room. Create a 30' X 16' family, a 14' X 14' bedroom, 10' X 10' laundry room and 8' X 8' 3/4 bathroom. Framing of 250 linear feet of walls. Walls and ceilings are painted drywall throughout. Exterior walls are insulated, painted trim throughout as well. Include MDF panel doors with passage locksets. Electrical wiring to code. Family room to include 8 recessed can lights and three surface mounted fixtures, wet bar and custom built-in cabinets, gas fireplace and Mohawk carpet. Bathroom to include new toilet, vanity with quartz top, tile flooring, tile shower, light/fan combination, lighting, surface mounted medicine cabinet and bath accessories.

	Qty.	Unit	Low Budget	High Budget
<b>01. Permits and Design</b>				
Permit	1	EA	\$ 2,956.25	\$ 3,399.69
Design and Planning Process -- See Design and Planning Agreement for Details.	1	EA	\$ 9,000.00	\$ 9,000.00
<b>Subtotal - Category 1</b>			<b>\$ 11,956.25</b>	<b>\$ 12,399.69</b>
<b>02. Site Prep and Demolition</b>				
Site Prep Small to Medium Project (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.	1	EA	\$ 446.55	\$ 513.53
Basement demolition of work area to EPA lead safe work practices: removal of interior walls, flooring to concrete, exterior walls to foundation, ceiling finish. Assumes no bath exists. Note- does not include asbestos removal- if needed, cost to be added.	1	EA	\$ 3,175.20	\$ 3,651.48
<i>NOTE: Although care is taken to carefully remove materials from wall and floor surfaces, screw pops, hairline cracks, and other issues can occasionally arise in adjacent spaces. No costs are included in this estimate to patch drywall or plaster or repaint walls in adjacent spaces but the need could arise and can be handled with a Change Order. We also use the most expensive and sensitive tape when taping prep to the floor, walls, or trim. If it is a bad or old finish, there is a small chance that it may peel some of the existing finish off. Any additional repairs will be an additional charge and dealt with via Change Order.</i>	1	Note	\$ 0.00	\$ 0.00
<b>Subtotal - Category 2</b>			<b>\$ 3,621.75</b>	<b>\$ 4,165.01</b>
<b>03. Landscaping and Fence - By Field Outdoor Spaces or homeowner</b>				
<b>Subtotal - Category 3</b>			<b>\$ -</b>	<b>\$ -</b>
<b>04. Concrete and Foundation</b>				
Fill in concrete on basement floor where rough-ins were done	15	SF	\$ 531.98	\$ 611.77
Option: Interior Drain tile and Sump Basket for <i>existing</i> basement floor. Includes removal of existing slab around the exterior, new drain tile, and sump basket. Add \$16,000 if needed.	0	LF	\$ 0.00	\$ 0.00
<b>Subtotal - Category 4</b>			<b>\$ 531.98</b>	<b>\$ 611.77</b>
<b>05. Masonry</b>				
<b>Subtotal - Category 5</b>			<b>\$ -</b>	<b>\$ -</b>

<b>06. Framing</b>			
Basic interior wall framing: Flatten walls and ceiling, fur out as needed, furnish and install backers for rock and accessories	1 EA	\$ 367.80	\$ 422.97
2x2 Fur wall and/or ceiling framing (materials and labor)	600 SF	\$ 2,679.30	\$ 3,081.20
Basement or Attic interior wall framing (materials and labor)	150 LF	\$ 6,930.45	\$ 7,970.02
<b>Subtotal - Category 6</b>		<b>\$ 9,977.55</b>	<b>\$ 11,474.18</b>
<b>09. Roofing, Flashing, Gutters</b>			
<b>Subtotal - Category 9</b>		\$ -	\$ -
<b>10. Exterior Trim, Porches and Decks</b>			
<b>Subtotal - Category 10</b>		\$ -	\$ -
<b>11. Siding, Soffit, and Fascia</b>			
<b>Subtotal - Category 11</b>		\$ -	\$ -
<b>12. Exterior Doors and Trim</b>			
<b>Subtotal - Category 12</b>		\$ -	\$ -
<b>13. Windows</b>			
Furnish and install basement glass block windows - No larger than 3'-0"x2'-0" NOTE: Assumes installed into cement foundation. Add \$ if in a limestone foundation. STYLE: Decora or ice scapes. 8 X 16 Vent (Y or N) NOTE: Decora is not as private as ice scapes	4 EA	\$ 2,638.20	\$ 3,033.93
Furnish and install new egress window well; includes excavation, cutting block and new corrugated window well OR treated timber well. Includes vinyl window. Tiering is additional. Well Type: WINDOW SPECS: Manufacturer: Line: Operation type, size, jamb, tempering, egress notes: see plan/schedule Exterior material /color: Interior material /color: Glass: clear Low E2 w/ Argon is standard- modify if something else desired Grids (type, size, pattern, color): Interior weather Strip color: ??? Hardware type/color: WOCD: Y or N (and specify color, if diff. from hardware) Screen surround material/color: Screen color: Exterior Brickmould profile/material/color/size: if comes with window, if not specify under	1 EA	\$ 3,406.25	\$ 3,917.19
<b>Subtotal - Category 13</b>		<b>\$ 6,044.45</b>	<b>\$ 6,951.12</b>
<b>14. Plumbing</b>			
<b>NOTE TO CLIENTS:</b> During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them. The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  <b>General Plumbing Note:</b> Any new waste or supply lines will be plastic, not copper or galvanized.	1 Note	\$ 0.00	\$ 0.00
Plumbing permit	1 EA	\$ 343.75	\$ 395.31
Hook up integral sink	1 EA	\$ 337.50	\$ 388.13
Furnish and install sink faucet; Sink faucet allowance \$300.00/ea. Manufacturer: Model #: Finish:	1 EA	\$ 765.85	\$ 880.73
Furnish and install a fiberglass shower pan only; Shower pan allowance \$300.00/ea. Manufacturer: Model #: Color:	1 EA	\$ 1,028.36	\$ 1,182.62
Furnish and install shower faucet, diverter and controller; Shower faucet package allowance \$300.00/set Manufacturer: Model #: Finish:	1 EA	\$ 928.36	\$ 1,067.62

Furnish and install toilet; Toilet allowance \$300.00/ea. <b>Manufacturer:</b> <b>Model #:</b> <b>Color:</b>	1 EA	\$ 765.86	\$ 880.74
Basement bathroom rough-in (base price); includes check valve and back flow preventer <b>Add concrete fill-in section above.</b>	1 EA	\$ 4,750.00	\$ 5,462.50
Demo existing cast iron or concrete laundry tub and related plumbing	1 EA	\$ 406.25	\$ 467.19
Furnish and install laundry sink; includes single, free standing utility tub laundry tub and basic faucet; Tub and faucet allowance \$150.00/set	1 EA	\$ 920.43	\$ 1,058.49
Basement laundry plumbing rough-in	1 EA	\$ 2,250.00	\$ 2,587.50
Option: Furnish and install an active radon mitigation system. Add \$3,450.00 if needed.	0 EA	\$ 0.00	\$ 0.00
<b>Subtotal - Category 14</b>		<b>\$ 12,496.36</b>	<b>\$ 14,370.82</b>
<b>15. HVAC</b>			
Mechanical permit	1 EA	\$ 312.50	\$ 359.38
Install new bathroom vent fan and vent to the exterior.	1 EA	\$ 875.00	\$ 1,006.25
Basement ducting - 2-bed rooms, family room, and bathroom; 1,100 sq. Ft	1 EA	\$ 3,468.75	\$ 3,989.06
Vent clothes dryer using corrosion resistant pipe; <i>Note - does not include dryer boost fan if the duct run is too long</i>	1 EA	\$ 618.75	\$ 711.56
<b>Subtotal - Category 15</b>		<b>\$ 5,275.00</b>	<b>\$ 6,066.25</b>
<b>16. Electrical</b>			
Electrical Permit	1 EA	\$ 231.25	\$ 265.94
<b>Specify device color:</b> <b>White, light almond, or ivory are standard. PICK ONE</b>	1 EA	\$ 0.00	\$ 0.00
<b>Specify switch style</b> <b>Pole or Decora. PICK ONE</b>			
Bathroom price for electrical (Includes GFCI Outlet to code, new switches and wiring in bath, and Lutron push button timer switch for the bath fan).	1 EA	\$ 1,875.00	\$ 2,156.25
<b>NOTE: Battery operated smoke detector and CO by homeowner. Will all need to be functional and placed per code. Code requires each floor have one smoke detector. In addition, any bedroom needs a smoke detector. Also there must be a carbon monoxide detector within 10 feet of each bedroom. **If the rest of the home does not meet the above code, homeowner will be responsible to update or if homeowner prefers, Castle will perform updates and a change order will be issued**</b>	1 Note	\$ 0.00	\$ 0.00
<b>NOTE: No wiring for security, doorbell, TV, speakers or phone is included in pricing. If any low voltage wires are found in a wall being opened up, additional costs to re-route them will occur.</b>	1 Note	\$ 0.00	\$ 0.00
CBR furnish and elec install above mirror light fixture; Fixture allowance \$100.00/ea. <b>Manufacturer:</b> <b>Model #:</b> <b>Finish:</b>	1 EA	\$ 272.50	\$ 313.38
CBR furnish and elec install light fixture; Fixture allowance \$250.00/ea. <b>Manufacturer:</b> <b>Model #:</b> <b>Finish:</b>	6 EA	\$ 2,850.00	\$ 3,277.50
<b>NOTE: For all home owner provided fixtures, there may be additional install costs for more complicated fixtures. ALL light fixtures must be specified prior to contract signing and be UL listed to pass inspection. All material issues related to materials supplied by owner are the responsibility of the owner to resolve. Extra trade partner trip charges may apply for return visits if material issues can not be resolved in timely manner.</b>	1 Note	\$ 0.00	\$ 0.00
Finished basement price for electrical	600 SF	\$ 7,875.00	\$ 9,056.25
Furnish and install new electric sub-panel	1 EA	\$ 875.00	\$ 1,006.25
Furnish and install recessed can lights	8 EA	\$ 1,150.00	\$ 1,322.50
<b>Subtotal - Category 16</b>		<b>\$ 15,128.75</b>	<b>\$ 17,398.06</b>

<b>17. Insulation</b>			
Rim joists 3" spray foam insulation; Please note - spray foam insulation requires people and pets to vacate the home for 24 hours while the insulation is curing	100 LF	\$ 750.00	\$ 862.50
Basement energy walls 2" spray foam insulation; Please note - spray foam insulation requires people and pets to vacate the home for 24 hours while the insulation is curing	700 SF	\$ 3,281.25	\$ 3,773.44
<b>Subtotal - Category 17</b>		<b>\$ 4,031.25</b>	<b>\$ 4,635.94</b>
<b>18. Drywall</b>			
Furnish and install 1/2" or 5/8" drywall on ceilings with smooth finish	600 SF	\$ 3,750.00	\$ 4,312.50
Furnish and install 1/2" drywall on walls with smooth finish	1950 SF	\$ 11,700.00	\$ 13,455.00
Boom/cartage fee for 2nd floor and basements	1 EA	\$ 331.25	\$ 380.94
<b>Subtotal - Category 18</b>		<b>\$ 15,781.25</b>	<b>\$ 18,148.44</b>
<b>19. Tile and Stone</b>			
Install tile backer underlayment on floor - thickness decided on-site	30 SF	\$ 264.60	\$ 304.29
Install tile on floor; - <b>Base Price:</b>	30 SF	\$ 1,082.55	\$ 1,244.93
<u>Tile allowance: \$6.50/SF</u>			
<b>Supplier:</b>			
<b>Spec#/description:</b>			
Install kerdi board tile backer. <b>Standard for shower or wet walls.</b>	63 SF	\$ 533.43	\$ 613.45
Install large format tile on shower surround walls using spacers.	63 SF	\$ 2,989.16	\$ 3,437.54
<u>Tile allowance: \$4.50/SF</u>			
<b>Supplier:</b>			
<b>Spec#/description:</b>			
Furnish and install accent tile, pattern TBD;	4 SF	\$ 307.93	\$ 354.12
<u>Tile allowance \$16.50/SF</u>			
<b>Supplier:</b>			
<b>Spec#/description:</b>			
Furnish and install bullnose tile, pattern TBD;	14 LF	\$ 214.79	\$ 247.01
<u>Tile allowance \$4.50/LF</u>			
<b>Supplier:</b>			
<b>Spec#/description:</b>			
Furnish and install Corian corner shelves in shower	2 EA	\$ 233.76	\$ 268.82
<b>Color: Glacier white or Bisque</b>			
GROUT - 25# Tec Power Grout	1 EA	\$ 71.31	\$ 82.01
<b>Color:</b>			
GROUT - 10# Tec Power Grout	1 EA	\$ 34.76	\$ 39.98
<b>Color:</b>			
Stock Material Costs - Denshield, Mud, Self Leveler, Mastic, Thinset, Redguard, Tape, Caulk, Sponges, Silicone, etc. <b>Include on all Tile projects.</b>	1 EA	\$ 515.02	\$ 592.27
<b>Subtotal - Category 19</b>		<b>\$ 6,247.32</b>	<b>\$ 7,184.42</b>
<b>20. Millwork, Doors, Hardware</b>			
Classic base molding - NOTE - Assumes 1X and top cap	240 LF	\$ 4,851.84	\$ 5,579.62
<b>Species:</b>			
<b>1X size:</b>			
<b>Top cap profile and height #:</b>			
<b>Brand/profile #:</b>			
Classic window and door casing - NOTE: Assumes 1X with a backband and a sill and stool on the windows	170 LF	\$ 3,117.97	\$ 3,585.67
<b>Species:</b>			
<b>Overall size:</b>			
<b>1X size:</b>			
<b>Backband brand/profile#:</b>			
<b>"Picture framed": Y or N</b>			
<b>Stool detail (thickness/extension) and apron detail (height, profile #):</b>			

Furnish and install wood jambs to an opening NOTE: The casing for the opening is on the window/door casing line Species: Jamb depth: Opening size:	20 LF	\$ 399.18	\$ 459.06
Furnish and install a pre-hung door Hinge finish: Species: Style: Brand/model#: Core: solid or hollow	4 EA	\$ 2,637.00	\$ 3,032.55
Furnish and install a bi-fold door. Figured PER set of 2 slabs. See jamb/stop line above. Jamb: wood or sheetrock opening Hinge finish: Species: Style: Brand/model #: Core: solid or hollow	1 EA	\$ 875.15	\$ 1,006.42
Furnish and install door knob/handle hardware Allowance: \$30.00 Manufacturer/model #: Style (locking, passage, etc.): Finish:	1 EA	\$ 75.28	\$ 86.57
Furnish and install door stop Allowance: \$5.00 Manufacturer/model #: Style (wall mount, hinge mount, etc.): Finish:	1 EA	\$ 16.32	\$ 18.77
Furnish and install bi-fold knob/handle hardware Allowance: \$20.00 Manufacturer/model #: Style: Finish:	4 EA	\$ 251.12	\$ 288.79
Furnish and install newel post Height: Species: Brand/model#:	1 EA	\$ 187.09	\$ 215.15
Furnish and install railing. Includes top rail, bottom rail, and spindles 4.5" O.C. Brand: Species: Top rail style/profile #: Bottom rail style/profile #: Spindle (balustrades) style/profile #: Fillet (Y or N)/profile #: Additional detail/profile #s:	16 LF	\$ 2,131.20	\$ 2,450.88
Furnish and install basic gripable handrail with mounting hardware Brand/profile #: Species: Hardware style/spec #: Hardware finish:	16 LF	\$ 338.78	\$ 389.60
Furnish and install a basic melamine closet organizational system	5 LF	\$ 828.85	\$ 953.18
<b>Subtotal - Category 20</b>		<b>\$ 15,709.78</b>	<b>\$ 18,066.25</b>

<b>21. Cabinetry, Countertops and Appliances</b>			
Furnish and install wall-mounted mirror/medicine cabinet. <u>Allowance: \$150.00</u> Manufacturer: Model/spec #: Color:	1 EA	\$ 306.95	\$ 352.99
Furnish and install stock bathroom vanity cabinet, counter/sink, and hardware <u>\$950.00</u> <u>Allowance</u> Manufacturer: Model #: Finish:	1 EA	\$ 1,492.55	\$ 1,716.43
Knobs and pulls will be installed on all cabinet doors and drawers. <u>Allowance: \$7.00/ea.</u> Manufacturer: Size: Model #: Finish:	8 EA	\$ 117.34	\$ 134.94
<b>CABINET SPECS:</b> Cabinet Line: Crystal Current or Crystal Keyline Box Type: Frameless, Framed, Inset Door Construction: MDF or Wood Door Style: Drawer Style: 5 piece or slab Drawer box construction: Interior material: select one- natural melamine on particle board substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on particle board substrate option for current frameless, or all plywood green core box with natural maple veneer if keyline; finished interiors of any cabinets would be noted on plans. Wood Species: Finish: paint or stain Color: Sheen: Specialties: (distressing, highlights, etc.) Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on drawing, not included. Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet	1 EA	\$ 0.00	\$ 0.00
<b>Crystal - Keyline line:</b> Furnish and install base cabinets -stained or painted wood	4 LF	\$ 2,096.00	\$ 2,410.40
<b>Crystal - Keyline line:</b> Furnish and install upper cabinets - stained or painted wood	4 LF	\$ 1,852.80	\$ 2,130.72
<b>Crystal - Keyline line:</b> Furnish and install pantry/linen cabinets - stained or painted wood	2 LF	\$ 2,671.20	\$ 3,071.88
Silestone quartz countertops will be installed. NOTE: Group C Color: Edge profile: Thickness: Undermount sink (Y or N):	8 SF	\$ 700.00	\$ 805.00
Silestone quartz 2-6" backsplash will be installed. NOTE: Group C Color: Height: Back Splash: Side splash (Y or N?):	4 LF	\$ 225.00	\$ 258.75
<b>APPLIANCES:</b> <i>NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.</i>	1 Note	\$ 0.00	\$ 0.00
Washer and dryer: Plumber to do all final hook-ups and install. Make/model #: Dimensions:	1 EA	\$ 300.00	\$ 345.00
<b>Subtotal - Category 21</b>		<b>\$ 9,761.84</b>	<b>\$ 11,226.11</b>

<b>22. Specialties</b>				
Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. <u>Classic.</u> <u>Allowance \$60.00.</u> Install included for 3 items. <b>Manufacturer:</b> <b>Model/spec #:</b> <b>Finish color:</b>	1 EA	\$ 213.55	\$ 245.58	
Standard size 3/8" frameless glass shower door. 28" wide x 71.5" tall. 8" tubular stock handle. Note: this is available in 71.5", 75.5", and 79.5" standard heights. NOTE: Finished tile to tile dimension should be 28 9/16" <b>Handle/hinge finish:</b> <b>Door height:</b>	1 EA	\$ 1,365.40	\$ 1,570.21	
<b>Subtotal - Category 22</b>		<b>\$ 1,578.95</b>	<b>\$ 1,815.79</b>	
<b>23. Flooring</b>				
Floor prep. Smoothing, leveling, etc.	1 HR	\$ 100.00	\$ 115.00	
Floor transitions. <b>Description</b> <b>Type:</b> <b>Finish:</b>	1 EA	\$ 94.10	\$ 108.22	
Upgraded quality carpet and pad will be installed. \$5.75/SF Allowance - Includes carpet AND pad <b>Manufacturer:</b> <b>Line/series:</b> <b>Color:</b>	600 SF	\$ 5,062.50	\$ 5,821.88	
<b>Subtotal - Category 23</b>		<b>\$ 5,256.60</b>	<b>\$ 6,045.09</b>	
<b>24. Painting and Decorating</b>				
Prime and painting ceilings using low VOC Paint. <b>COLOR: Standard flat ceiling white</b>	636 SF	\$ 1,231.87	\$ 1,416.65	
Prime and paint walls using low VOC Paint. <b>Manufacturer:</b> <b>Color name and #:</b> <b>Sheen:</b>	2200 SF	\$ 2,823.48	\$ 3,247.00	
Priming and painting of base molding and/or casing. <u>NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.</u> <b>Manufacturer:</b> <b>Color name and #:</b> <b>Sheen: (satin is standard)</b>	410 LF	\$ 3,019.65	\$ 3,472.60	
Priming and painting of a door <u>both sides.</u> Includes the jamb of the unit. <u>NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.</u> <b>Manufacturer:</b> <b>Color name and #:</b> <b>Sheen: (satin is standard)</b>	5 EA	\$ 1,148.50	\$ 1,320.78	
Priming and painting on interior side of window, <b>one side.</b> <u>NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.</u> <b>Manufacturer:</b> <b>Color name and #:</b> <b>Sheen: (satin is standard)</b>	1 EA	\$ 390.30	\$ 448.85	
<b>NOTE: Please note that when the homeowner is doing the painting, they are responsible for caulking, filling nail holes, and repairing minor wall and ceiling dings. There will need to be a few rounds of touch-ups, due to the nature of construction, and that falls under the scope of the painter.</b>	1 Note	\$ 0.00	\$ 0.00	
<b>Subtotal - Category 24</b>		<b>\$ 8,613.80</b>	<b>\$ 9,905.87</b>	

<b>25. Clean Up and Debris Removal</b>					
Disposal and clean-up - remove all site prep, wipe down and broom sweep area. Haul all extra material off site.	1 EA	\$ 987.31	\$ 1,135.41		
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved. <u>NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.</u>	3 MO	\$ 240.00	\$ 240.00		
<u>ADD number of days, dumpster is estimated to be needed over 30 days</u>	60 DAYS	\$ 420.00	\$ 420.00		
<b>DUMPSTER NOTE:</b> If the dumpster is placed on the street, and the city calls a snow emergency or street cleaning, there will be an additional \$200 charge per move or violation via a change order. Sometimes it will get moved, sometimes it will just get fined. The charge is the same either way.	0 EA	\$ 0.00	\$ 0.00		
10 Yard mini roll-off dumpster - smaller truck for smaller places 2.5 ton maximum <b>NOTE:</b> for 30 days only. Use line above for estimated days over 30 days	1 EA	\$ 337.50	\$ 388.13		
20 Yard roll-off dumpster - 10 ton maximum <b>NOTE:</b> for 30 days only. Use line above for estimated days over 30 days	1 EA	\$ 418.75	\$ 481.56		
<b>Subtotal - Category 25</b>		<b>\$ 2,403.56</b>	<b>\$ 2,665.10</b>		
<b>Project Subtotal</b>		<b>\$ 134,581.44</b>	<b>\$ 153,129.90</b>		
<b>26. Designer Oversight &amp; Project Management</b>		\$ 14,703.02	\$ 16,908.48		
<b>27. Overhead and Profit</b>		\$ 21,095.64	\$ 24,259.99		
<b>Grand Total**</b>		<b>\$ 170,380.10</b>	<b>\$ 195,937.12</b>		
<p>MN License # BC005657</p> <p><b>**Important Notice**</b></p> <p><b>**This is only a ballpark guesstimate. This does not represent actual prices, only a best guess based on Castle's past experiences. There are still many unknowns that can affect pricing at this point.</b></p>					
<b>Check or Cash Discount Low 2.5%*</b>	<b>\$ 4,259.50</b>	<b>Check or Cash Discount High 2.5%*</b>	<b>\$ 4,898.43</b>	<b>\$ 166,120.60</b>	<b>\$ 191,038.69</b>

\*Doesn't Apply to Bank Financing or loan process that requires Castle to receive payment directly from that entity after Castle has paid subcontractors and secured lien waivers. In these instances Castle essentially acts as



## Custom Design Showrooms



5 W. Diamond Lake Rd  
Minneapolis, MN 55419  
P) 612-789-8509



2600 Johnson St. NE  
Minneapolis, MN 55418  
P) 612-789-8509




362 Snelling Ave S.  
St. Paul, MN 55105  
P) 651-699-4164



4020 Minnehaha Ave  
Minneapolis, MN 55406  
P) P) 612-789-8509

Showroom maps & hours can be found on our website at [www.CASTLEBRI.com](http://www.CASTLEBRI.com)



## Need Help with Financing Options?

guaranteedRate<sup>®</sup>

ALERUS  
MORTGAGE

TRADITION  
mortgage

Financial  
ONE  
CREDIT UNION

<https://www.castlebri.com/financing-options/>

## Castle Offers Financing

\$ Up to \$25k or  
50% of project cost

% 7% interest rate

60 Up to 60 month term

Completely  
unsecured loan

No fees, closing costs or  
prepayment penalties

On approved credit  
Requires ACH payment

Find out if  
you qualify

Call or email Tandra Heine, Financial Controller at 612.877.8374 or  
[Tandra@castlebri.com](mailto:Tandra@castlebri.com) to schedule your 10 minute no obligation consultation.