**Bathroom Remodel- Classic (Gut to Studs)** 

Address:

City, State, Zip:

Phone:

Email:



### **BUDGET ANALYSIS**

Project Description: Date: 6/8/2022

35SF bathroom gutted to the studs. Bathroom remodel to include new window, insulation, sheetrock, electrical, plumbing fixtures, tub with subway tile shower walls, tile floor, vanity/top, millwork, recessed medicine cabinet, accessories, painting, clean-up and debris removal.

O1. Permits and Design  Permit Design and Planning Process See Design and Planning Agreement for Details.  Subtotal - Category 1  O2. Site Prep and Demolition  Site Prep Small to Medium Project (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.  Bathroom demolition of work area to EPA lead safe work practices: Demo existing cabinets, accessories, fixtures, and trim. Demo existing walls to the studs. Demo existing flooring and subfloor. Existing ceiling to remain and new drywall to be overlaid on the existing. Items to be removed/saved for reinstallation:  OPTION: Furnish and install a Schlage "Camelot" keypad electronic deadbolt. Finish: TBD ADD: \$110.00  NOTE: This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your designer for details.	1 EA 1 EA	\$	1,172.50		
Permit Design and Planning Process See Design and Planning Agreement for Details.  Subtotal - Category 1  02. Site Prep and Demolition Site Prep Small to Medium Project (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.  Bathroom demolition of work area to EPA lead safe work practices: Demo existing cabinets, accessories, fixtures, and trim. Demo existing walls to the studs. Demo existing flooring and subfloor. Existing ceiling to remain and new drywall to be overlaid on the existing. Items to be removed/saved for reinstallation:  OPTION: Furnish and install a Schlage "Camelot" keypad electronic deadbolt. Finish: TBD ADD: \$110.00  NOTE: This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your			1.172 50		
Design and Planning Process See Design and Planning Agreement for Details.  Subtotal - Category 1  02. Site Prep and Demolition  Site Prep Small to Medium Project (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.  Bathroom demolition of work area to EPA lead safe work practices: Demo existing cabinets, accessories, fixtures, and trim. Demo existing walls to the studs. Demo existing flooring and subfloor. Existing ceiling to remain and new drywall to be overlaid on the existing. Items to be removed/saved for reinstallation:  OPTION: Furnish and install a Schlage "Camelot" keypad electronic deadbolt. Finish: TBD ADD: \$110.00  NOTE: This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your				\$	1,348.38
Subtotal - Category 1  02. Site Prep and Demolition  Site Prep Small to Medium Project (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.  Bathroom demolition of work area to EPA lead safe work practices: Demo existing cabinets, accessories, fixtures, and trim. Demo existing walls to the studs. Demo existing flooring and subfloor. Existing ceiling to remain and new drywall to be overlaid on the existing. Items to be removed/saved for reinstallation:  OPTION: Furnish and install a Schlage "Camelot" keypad electronic deadbolt. Finish: TBD ADD: \$110.00  NOTE: This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your	1 LA	Ψ	3,400.00	\$	3,400.00
O2. Site Prep and Demolition  Site Prep Small to Medium Project (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.  Bathroom demolition of work area to EPA lead safe work practices: Demo existing cabinets, accessories, fixtures, and trim. Demo existing walls to the studs. Demo existing flooring and subfloor. Existing ceiling to remain and new drywall to be overlaid on the existing. Items to be removed/saved for reinstallation:  OPTION: Furnish and install a Schlage "Camelot" keypad electronic deadbolt. Finish: TBD ADD: \$110.00  NOTE: This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your			3,400.00	Ψ	3,400.00
Site Prep Small to Medium Project (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.  Bathroom demolition of work area to EPA lead safe work practices: Demo existing cabinets, accessories, fixtures, and trim. Demo existing walls to the studs. Demo existing flooring and subfloor. Existing ceiling to remain and new drywall to be overlaid on the existing. Items to be removed/saved for reinstallation:  OPTION: Furnish and install a Schlage "Camelot" keypad electronic deadbolt. Finish: TBD ADD: \$110.00  NOTE: This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your		\$	4,572.50	\$	4,748.38
tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.  Bathroom demolition of work area to EPA lead safe work practices: Demo existing cabinets, accessories, fixtures, and trim. Demo existing walls to the studs. Demo existing flooring and subfloor. Existing ceiling to remain and new drywall to be overlaid on the existing. Items to be removed/saved for reinstallation:  OPTION: Furnish and install a Schlage "Camelot" keypad electronic deadbolt. Finish: TBD ADD: \$110.00  NOTE: This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your					
accessories, fixtures, and trim. Demo existing walls to the studs. Demo existing flooring and subfloor. Existing ceiling to remain and new drywall to be overlaid on the existing. Items to be removed/saved for reinstallation:  OPTION: Furnish and install a Schlage "Camelot" keypad electronic deadbolt. Finish: TBD ADD: \$110.00  NOTE: This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your	1 EA	\$	446.55	\$	513.53
ADD: \$110.00  NOTE: This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your	1 EA	\$	2,116.80	\$	2,434.32
	1 EA	\$	0.00	\$	0.00
NOTE: Although care is taken to carefully remove materials from wall and floor surfaces, screw pops, hairline cracks, and other issues can occasionally arise in adjacent spaces. No costs are included in this estimate to patch drywall or plaster or repaint walls in adjacent spaces but the need could arise and can be handled with a Change Order. We also use the most expensive and sensitive tape when taping prep to the floor, walls, or trim. If it is a bad or old finish, there is a small chance that it may peel some of the existing finish off. Any additional repairs will be an additional charge and dealt with via Change Order.	1 Note	\$	0.00	\$	0.00
Subtotal - Category 2		\$	2,563.35	\$	2,947.85
03. Landscaping and Fence - By Field Outdoor Spaces or homeowner					
Subtotal - Category 3		\$	-	\$	-
04. Concrete and Foundation					
Subtotal - Category 4		\$	-	\$	-
05. Masonry					
Subtotal - Category 5		\$	-	\$	-
66. Framing Basic bath framing line: Flatten walls and ceiling, fur out as needed, replace subfloor, furnish and install backers for rock and accessories, frame one niche or med chest; add additional lines below if applicable.	1 EA	\$	2,014.00	\$	2,316.10
Subtotal - Category 6					
09. Roofing, Flashing, Gutters		\$	2,014.00	\$	2,316.10

		\$		\$	
xterior Trim, Porches and Decks					
otal - Category 10		\$	-	\$	-
iding, Soffit, and Fascia otal - Category 11		\$		\$	
xterior Doors and Trim		, J	-	J	-
otal - Category 12		\$	-	\$	-
Vindows					
Furnish and install new custom size top of line vinyl or fiberglass pocket insert window; tempered glass.  Window allowance \$725.00/ea.  Manufacturer:  Line:  Operation type, size, jamb, tempering, egress notes: see plan/schedule  Exterior material /color:  Interior material /color:	1 EA	\$	1,233.00	\$	1,417.9
Glass: clear Low E2 w/ Argon is standard- modify if something else desired Grids (type, size, pattern, color): Interior weather Strip color: ??? Hardware type/color: WOCD: Y or N (and specify color, if diff. from hardware) Screen surround material/color: Screen color:					
Window install material (flashing, caulk, shims, etc.)	1 EA	\$	62.50	\$	71.8
otal - Category 13		\$	1,295.50	\$	1,489.8
lumbing  NOTE TO CLIENTS: During kitchen and bathroom remodels, the pipes (drains and galvanized water lines) sit for extended periods of time with no water going through them.	1 Note	\$	0.00	\$	0.0
The build up on the inside of the pipes dries up and sometimes can come free and clog either a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or					
a drain or water line, once the water is turned back on at the end of the project. There is no	1 EA	\$	343.75	\$	395.
a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.	1 EA 1 EA	\$	343.75 585.95	\$	
a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install an under mount vanity sink Sink Allowance: \$160.00  Manufacturer: Model #  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #:				\$	673.
a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install an under mount vanity sink  Sink Allowance: \$160.00  Manufacturer:  Model #  Furnish and install sink faucet;  Sink faucet allowance \$300.00/ea.  Manufacturer:	1 EA	\$	585.95	\$	673. 880.
a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install an under mount vanity sink Sink Allowance: \$160.00  Manufacturer: Model #  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea.  Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea.  Drain side: Manufacturer: Model #:	1 EA	\$	585.95 765.85	\$	880. 2,245.
a drain or water line, once the water is turned back on at the end of the project. There is no money included to unclog a pipe if this happens and additional charges will occur.  General Plumbing Note: Any new waste or supply lines will be plastic, not copper or galvanized.  Plumbing permit  Furnish and install an under mount vanity sink Sink Allowance: \$160.00 Manufacturer: Model #  Furnish and install sink faucet; Sink faucet allowance \$300.00/ea. Manufacturer: Model #: Finish: Furnish and install 5' cast iron tub; Tub allowance \$500.00/ea. Drain side: Manufacturer: Model #: Finish: Furnish and install tub waste and overflow Model #: Firnish:	1 EA 1 EA	\$ \$ \$	585.95 765.85 1,952.65	\$	395. 673. 880. 2,245.

Change out existing 1 1/2" drain to a 2" drain as required by code and misc. RI updates.  NOTE: This is required for ALL new tub installs and tub to shower conversions where the plumbing is accessible from below (unfinished basement)	1 EA	\$ 1,500.00	\$	1,725.00
Subtotal - Category 14		\$ 7,115.14	\$	8,182.41
5. HVAC				
Mechanical permit	1 EA	\$ 312.50	\$	359.38
Install new bathroom vent fan and vent to the exterior.	1 EA	\$ 875.00	\$	1,006.25
Furnish and install new register cover - • Hvac register cover- shoemaker manufacturer, select standard color of white or driftwood tan (a medium brown/tan); or can do designer colors of almond, Navajo white, vanilla, coffee tan, camero silver, bronze, or black velvet for approx. \$14 more and 3-4 week lead time.  Color:	1 EA	\$ 31.39	\$	36.10
ubtotal - Category 15		\$ 1,218.89	\$	1,401.72
6. Electrical				
Electrical Permit	1 EA	\$ 231.25	\$	265.94
Specify device color:	1 EA	\$ 0.00	\$	0.00
White, light almond, or ivory are standard. PICK ONE  Specify switch style Pole or Decora. PICK ONE			Ť	
Bathroom price for electrical (Includes GFCI Outlet to code, new switches and wiring in bath, and Lutron push button timer switch for the bath fan).	1 EA	\$ 1,875.00	\$	2,156.25
NOTE: Battery operated smoke detector and CO by homeowner. Will all need to be functional and placed per code. Code requires each floor have one smoke detector. In addition, any bedroom needs a smoke detector. Also there must be a carbon monoxide detector within 10 feet of each bedroom. **If the rest of the home does not meet the above code, homeowner will be responsible to update or if homeowner prefers, Castle will perform updates and a change order will be issued**"	1 Note	\$ 0.00	\$	0.00
NOTE: No wiring for security, doorbell, TV, speakers or phone is included in pricing. If any low voltage wires are found in a wall being opened up, additional costs to re-route them will occur.	1 Note	\$ 0.00	\$	0.00
CBR furnish and elec install above mirror light fixture;  Fixture allowance \$100.00/ea.  Manufacturer:  Model #:  Finish:	1 EA	\$ 272.50	\$	313.38
NOTE: For all home owner provided fixtures, there may be additional install costs for more complicated fixtures. ALL light fixtures must be specified prior to contract signing and be UL listed to pass inspection. All material issues related to materials supplied by owner are the responsibility of the owner to resolve. Extra trade partner trip charges may apply for return visits if material issues can not be resolved in timely manner.	1 Note	\$ 0.00	\$	0.00
CBR furnish, HVAC install, and Elec wire bath fan: Panasonic, • FV-0510VS1 Whisper Value 50/80/100 CFM Low Profile, 0.3-1.3 sones, 3 3/8" Housing Depth - UL listed for wall and ceiling installation, Energy Star Qualified - DC Fan Motor See hvac for install/venting.	1 EA	\$ 313.78	\$	360.84
Subtotal - Category 16		\$ 2,692.53	\$	3,096.40
7. Insulation				
Basic Bath Insulation - Furnish and install R-13 or R-19 batt insulation, depending on the cavity size, in the exterior walls and 4mil poly, foam window (if required) and foam ceiling/floor penetrations to code	1 EA	\$ 404.95	\$	465.69
ubtotal - Category 17		\$ 404.95	\$	465.69
8. Drywall  Furnish and install 1/2" or 5/8" drywall on the ceilings with smooth finish	35 SF	\$ 511.18	\$	587.85
Furnish and install 1/2" drywall on walls with smooth finish	152 SF	\$ 1,254.91	\$	1,443.15
ubtotal - Category 18		\$ 1,766.09	\$	2,031.00
9. Tile and Stone				
Install tile backer underlayment on floor - thickness decided on-site	23 SF	\$ 202.86	\$	233.29

Install tile on floor; - Base Price: <u>Tile allowance: \$6.50/SF</u>	23 SF	\$	829.96	\$	954
Supplier: Spec#/description: Furnish and install Corian single bevel threshold - 36" long, approx. 1 3/4" wide	1 EA	\$	152.92	\$	175
Color: glacier white or bisque Thickness: 1/4" or 1/2"					
Install kerdi board tile backer. Standard for shower or wet walls.	70 SF	\$	592.70	\$	68
Install large format tile on shower surround walls using spacers.  Tile allowance: \$4.50/SF  Supplier: Spec#/description:	70 SF	\$	3,136.07	\$	3,60
Furnish and install tiled niche in tub/shower area. 6"x12", 12"x12", 20"x12", or 28"x12" premade schluter niches. These are meant to fit btw 16" o.c. framing.  Note - tile material cost is in the SF above	1 EA	\$	484.89	\$	55
Tile edging - (figured per 8' stick)  Manufacturer: Schluter  Style: Jolly  Thickness: to match tile	3 EA	\$	166.63	\$	19
Finish: Satin Nickel / Chrome / Painted Included (Others at Upgrade)					
GROUT - 10# Tec Power Grout Color:	2 EA	\$	69.53	\$	7
Stock Material Costs - Denshield, Mud, Self Leveler, Mastic, Thinset, Redguard, Tape, Caulk, Sponges, Silicone, etc. <b>Include on all Tile projects.</b>	1 EA	\$	516.93	\$	59
l - Category 19		\$	6,152.48	\$	7,07
work, Doors, Hardware	1 74	¢	44.10	6	
Rehang existing door	1 EA	\$	44.10	\$	
Base shoe molding Species:	16 LF	\$	89.76	\$	10
	16 LF	\$	89.76	\$	10
Species: Size: Brand/profile #: Classic base molding - NOTE - Assumes 1X and top cap Species:	16 LF 16 LF	\$	89.76 365.79	\$	
Species: Size: Brand/profile #:  Classic base molding - NOTE - Assumes 1X and top cap Species: 1X size: Top cap profile and height #: Brand/profile #:	16 LF	\$	365.79	\$	42
Species: Size: Brand/profile #:  Classic base molding - NOTE - Assumes 1X and top cap Species: 1X size: Top cap profile and height #: Brand/profile #:  Classic window and door casing - NOTE: Assumes 1X with a backband and a sill and stool on the windows Species: Overall size: 1X size:					42
Species: Size: Brand/profile #:  Classic base molding - NOTE - Assumes 1X and top cap Species: 1X size: Top cap profile and height #: Brand/profile #:  Classic window and door casing - NOTE: Assumes 1X with a backband and a sill and stool on the windows Species: Overall size:	16 LF	\$	365.79	\$	42
Species: Size: Brand/profile #:  Classic base molding - NOTE - Assumes 1X and top cap Species: 1X size: Top cap profile and height #: Brand/profile #:  Classic window and door casing - NOTE: Assumes 1X with a backband and a sill and stool on the windows Species: Overall size: 1X size: Backband brand/profile#: "Picture framed": Y or N Stool detail (thickness/extension) and apron detail (height, profile #): Furnish and install door knob/handle hardware Allowance: \$30.00 Manufacturer/model #: Style (locking, passage, etc.):	16 LF	\$	365.79	\$	92
Species: Size: Brand/profile #:  Classic base molding - NOTE - Assumes 1X and top cap Species: 1X size: Top cap profile and height #: Brand/profile #:  Classic window and door casing - NOTE: Assumes 1X with a backband and a sill and stool on the windows Species: Overall size: 1X size: Backband brand/profile#: "Picture framed": Y or N Stool detail (thickness/extension) and apron detail (height, profile #): Furnish and install door knob/handle hardware Allowance: \$30.00 Manufacturer/model #:	16 LF 40 LF	<b>s</b>	365.79 804.20	\$	92
Species: Size: Brand/profile #:  Classic base molding - NOTE - Assumes 1X and top cap Species: 1X size: Top cap profile and height #: Brand/profile #:  Classic window and door casing - NOTE: Assumes 1X with a backband and a sill and stool on the windows Species: Overall size: 1X size: Backband brand/profile#: "Picture framed": Y or N Stool detail (thickness/extension) and apron detail (height, profile #): Furnish and install door knob/handle hardware Allowance: \$30.00 Manufacturer/model #: Style (locking, passage, etc.): Finish:  Furnish and install door stop Allowance: \$5.00 Manufacturer/model #:	16 LF 40 LF	<b>s</b>	365.79 804.20	\$	92
Species: Size: Brand/profile #:  Classic base molding - NOTE - Assumes 1X and top cap Species: 1X size: Top cap profile and height #: Brand/profile #:  Classic window and door casing - NOTE: Assumes 1X with a backband and a sill and stool on the windows Species: Overall size: 1X size: Backband brand/profile#: "Picture framed": Y or N Stool detail (thickness/extension) and apron detail (height, profile #): Furnish and install door knob/handle hardware Allowance: \$30.00 Manufacturer/model #: Style (locking, passage, etc.): Finish:  Furnish and install door stop Allowance: \$5.00	16 LF 40 LF 1 EA	\$ \$	365.79 804.20 75.28	\$ \$	92 92

:					
pinetry, Countertops and Appliances	1.50		20605	Φ.	2.52
Furnish and install wall-mounted mirror/medicine cabinet.	1 EA	\$	306.95	\$	352.
Allowance. \$150.00					
Manufacturer:					
Model/spec #:					
Color:					
Knobs and pulls will be installed on all cabinet doors and drawers.	6 EA	\$	88.00	\$	101
Allowance: \$7.00/ea.					
Manufacturer:					
Size:					
Model #:					
Finish:					
Walls I I I I I I	1.54		264.60		204
Meet delivery, unload, and unpack cabinets.	1 EA	\$	264.60	\$	304
CABINET SPECS:	1 EA	\$	0.00	\$	0
Cabinet Line: Crystal Current or Crystal Keyline					
Box Type: Frameless, Framed, Inset					
Door Construction: MDF or Wood					
Door Style:					
Drawer Style: 5 piece or slab					
Drawer box construction: Interior material: select one- natural melamine on particle board		1			
substrate standard or natural basswood veneer on plywood substrate upgrade, white melamine on		1			
particle board substrate option for current frameless, or all plywood green core box with natural					
maple veneer if keyline; finished interiors of any cabinets would be noted on plans.					
Wood Species:					
Finish: paint or stain					
Color:					
Sheen:					
Specialties: (distressing, highlights, etc.)					
Crown:					
Shoe: Yes					
Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished					
Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on					
drawing, not included.					
Any accessories will be noted on plan. If accessory provided by Castle and not Cabinet					
Crystal - Current line: Furnish and install vanity base cabinets - stained or painted wood	3 LF	\$	962.10	\$	1,106
, i		'			ĺ
Silestone quartz countertops will be installed. NOTE: Group C	6 SF	\$	525.00	\$	603
Color:					
Edge profile:					
Thickness:					
Undermount sink (Y or N):					
	2.7.5		1.00.77		10
Silestone quartz 2-6" backsplash will be installed. NOTE: Group C	3 LF	\$	168.75	\$	194
Color:					
Height:					
Back Splash:		1			
Cide onlock (V on N2).					
Side splash (Y or N?):					
	1 Note	s	0.00	S	(
APPLIANCES:	1 Note	\$	0.00	\$	(
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they	1 Note	\$	0.00	\$	(
APPLIANCES:  NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in	1 Note	\$	0.00	\$	C
APPLIANCES:	1 Note	\$	0.00	\$	(
APPLIANCES:  NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.	1 Note	\$			
APPLIANCES:  NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.	1 Note		2,315.40		
APPLIANCES:  NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.	1 Note				2,662
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.  1 - Category 21 cialties		\$	2,315.40	\$	2,662
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.  1 - Category 21 cialties Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. Classic.		\$	2,315.40	\$	2,662
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.  I - Category 21 citalties Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. Classic. Allowance \$60.00. Install included for 3 items. Manufacturer:		\$	2,315.40	\$	2,662
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.  1 - Category 21 cialties Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. Classic. Allowance \$60.00. Install included for 3 items.		\$	2,315.40	\$	2,662
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.  1 - Category 21 ialties Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. Classic. Allowance \$60.00. Install included for 3 items. Manufacturer: Model/spec #:		\$	2,315.40	\$	2,662
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.  1- Category 21  italties  Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. Classic.  Allowance \$60.00. Install included for 3 items.  Manufacturer: Model/spec #: Finish color:	1 EA	\$	<b>2,315.40</b> 213.55	\$	<b>2,662</b>
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.  1 - Category 21  cialties  Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. Classic.  Allowance \$60.00. Install included for 3 items.  Manufacturer: Model/spec #: Finish color:  Furnish and install a permanent, screw in shower curtain rod		\$	2,315.40	\$	<b>2,662</b>
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.  1- Category 21  Stalties  Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. Classic. Allowance \$60.00. Install included for 3 items.  Manufacturer: Model/spec #: Finish color:  Furnish and install a permanent, screw in shower curtain rod Manufacturer:	1 EA	\$	<b>2,315.40</b> 213.55	\$	<b>2,662</b>
APPLIANCES: NOTE: Client to communicate with appliance supplier regarding delivery of appliances they purchased and arrange to meet/receive delivery themselves. The project manager will be in communication with client regarding that timing.  1 - Category 21  Stalties  Furnish bathroom accessories - 24" towel bar, towel ring and toilet paper holder. Classic. Allowance \$60.00. Install included for 3 items.  Manufacturer: Model/spec #: Finish color:  Furnish and install a permanent, screw in shower curtain rod	1 EA	\$	<b>2,315.40</b> 213.55	\$	2,662 245

		\$	360.27	\$	414.31
23. Flooring					
Subtotal - Category 23		\$	-	\$	-
24. Painting and Decorating In house set up, prep, clean up	1 EA	\$	384.05	\$	441.66
Prime and painting ceilings using low VOC Paint.  COLOR: Standard flat ceiling white	35 SF	\$	104.84	\$	120.56
Prime and paint walls using low VOC Paint.  Manufacturer:  Color name and #:  Sheen:	152 SF	\$	237.09	\$	272.65
Priming and painting of base molding and/or casing. NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)	56 LF	\$	468.83	\$	539.16
Priming and painting of a door <u>both sides</u> . Includes the jamb of the unit. <u>NOTE: Our standard is low VOC for woodwork</u> , although may not be able to use low VOC primer due to existing <u>stain/wood condition- tbd</u> . Will use low VOC primer when able.  Manufacturer: Color name and #: Sheen: (satin is standard)	1 EA	\$	229.70	\$	264.16
NOTE: Please note that when the homeowner is doing the painting, they are responsible for caulking, filling nail holes, and repairing minor wall and ceiling dings. There will need to be a few rounds of touch-ups, due to the nature of construction, and that falls under the scope of the painter.	1 Note	\$	0.00	\$	0.00
Subtotal - Category 24		\$	1,424.51	\$	1,638.18
25. Clean Up and Debris Removal  Disposal and clean-up - remove all site prep, wipe down and broom sweep area. Haul all extra material off site.	1 EA	\$		•	
material Off Site.			422.63	\$	486.02
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.	2 MO	\$	422.63 160.00	\$	486.02 160.00
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.		\$	160.00	\$	160.00
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be	2 MO 30 DAYS 0 EA				
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.  ADD number of days, dumpster is estimated to be needed over 30 days  DUMPSTER NOTE: If the dumpster is placed on the street, and the city calls a snow emergency or street cleaning, there will be an additional \$200 charge per move or violation via a change order. Sometimes it will get moved, sometimes it will just get fined. The charge is the	30 DAYS	<b>\$ \$</b>	160.00 210.00	\$	160.00 210.00
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.  ADD number of days, dumpster is estimated to be needed over 30 days.  DUMPSTER NOTE: If the dumpster is placed on the street, and the city calls a snow emergency or street cleaning, there will be an additional \$200 charge per move or violation via a change order. Sometimes it will get moved, sometimes it will just get fined. The charge is the same either way.	30 DAYS 0 EA	\$ \$ \$	160.00 210.00 0.00	\$ \$ \$	160.00 210.00 0.00
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.  ADD number of days, dumpster is estimated to be needed over 30 days  DUMPSTER NOTE: If the dumpster is placed on the street, and the city calls a snow emergency or street cleaning, there will be an additional \$200 charge per move or violation via a change order. Sometimes it will get moved, sometimes it will just get fined. The charge is the same either way.  10 Yard mini roll-off dumpster - smaller truck for smaller places 2.5 ton maximum NOTE: for 30 days only. Use line above for estimated days over 30 days  Regular portable restroom (one month)  NOTE: This cost can be saved if home owner is ok with making a bathroom in the house	30 DAYS 0 EA 1 EA	\$ \$ \$	210.00 0.00 337.50	s s s	210.00 0.00 388.13
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.  ADD number of days, dumpster is estimated to be needed over 30 days.  DUMPSTER NOTE: If the dumpster is placed on the street, and the city calls a snow emergency or street cleaning, there will be an additional \$200 charge per move or violation via a change order. Sometimes it will get moved, sometimes it will just get fined. The charge is the same either way.  10 Yard mini roll-off dumpster - smaller truck for smaller places 2.5 ton maximum NOTE: for 30 days only. Use line above for estimated days over 30 days  Regular portable restroom (one month)  NOTE: This cost can be saved if home owner is ok with making a bathroom in the house available to Castle and it's trade partners	30 DAYS 0 EA 1 EA	\$ \$ \$	160.00 210.00 0.00 337.50 425.00	s s s	160.00 210.00 0.00 388.13 488.75
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.  ADD number of days, dumpster is estimated to be needed over 30 days  DUMPSTER NOTE: If the dumpster is placed on the street, and the city calls a snow emergency or street cleaning, there will be an additional \$200 charge per move or violation via a change order. Sometimes it will get moved, sometimes it will just get fined. The charge is the same either way.  10 Yard mini roll-off dumpster - smaller truck for smaller places 2.5 ton maximum NOTE: for 30 days only. Use line above for estimated days over 30 days  Regular portable restroom (one month)  NOTE: This cost can be saved if home owner is ok with making a bathroom in the house available to Castle and it's trade partners  Subtotal - Category 25	30 DAYS 0 EA 1 EA	\$ \$ \$ \$	160.00 210.00 0.00 337.50 425.00	s s s s s s	160.00 210.00 0.00 388.13 488.75
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.  NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.  ADD number of days, dumpster is estimated to be needed over 30 days  DUMPSTER NOTE: If the dumpster is placed on the street, and the city calls a snow emergency or street cleaning, there will be an additional \$200 charge per move or violation via a change order. Sometimes it will get moved, sometimes it will just get fined. The charge is the same either way.  10 Yard mini roll-off dumpster - smaller truck for smaller places 2.5 ton maximum NOTE: for 30 days only. Use line above for estimated days over 30 days  Regular portable restroom (one month)  NOTE: This cost can be saved if home owner is ok with making a bathroom in the house available to Castle and it's trade partners  Subtotal - Category 25  Project Subtotal	30 DAYS 0 EA 1 EA	\$ \$ \$ \$ \$ \$	160.00 210.00 0.00 337.50 425.00 1,555.13 36,938.68	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	160.00 210.00 0.00 388.13 488.75 1,732.90 41,807.61

#### MN License # BC005657

Showroom maps & hours can be found on our website at www.CASTLEBRI.com

\*\*Important Notice\*\*

\*\*This is only a ballpark guesstimate. This does not represent actual prices, only a best guess based on Castle's past experiences. There are still many unknowns that can affect pricing at this point.

Check or Cash Discount Low	\$ 1,182.04	Check or Cash	\$ 1,359.34	\$ 46,099.48	\$ 53,014.40
2.5%*		Discount High			
2.570		2.5%*			

<sup>\*</sup>Doesn't Apply to Bank Financing or loan process that requires Castle to receive payment directly from that entity after Castle has paid subcontractors and secured lien waivers. In these instances Castle essentially acts as

#### **Custom Design Showrooms**



5 W. Diamond Lake Rd Minneapolis, MN 55419 P) 612-789-8509



2600 Johnson St. NE Minneapolis, MN 55418 P) 612-789-8509



362 Snelling Ave S. St. Paul, MN 55105 P) 651-699-4164



4020 Minnehaha Ave Minneapolis, MN 55406 P) P) 612-789-8509



# Need Help with Financing Options?









https://www.castlebri.com/financing-options/

## **Castle Offers Financing**



Find out if you qualify

Call or email Tambra Heine, Financial Controller at 612.877.8374 or Tambra@castlebri.com to schedule your 10 minute no obligation consultation.