

Name: Deck Addition

Address:

City, State, Zip:

Phone:

Email:



BUDGET ANALYSIS

Project Description:

Date: 11/7/2021

Build a new 24' x 10' cedar deck in the back yard per plan. Demo wall and frame new header for a new 5'-0" patio door.

	Qty.	Unit	Low Budget	High Budget
01. Permits and Design				
Permit	1	EA	\$ 812.50	\$ 893.75
Design and Planning Process -- See Design and Planning Agreement for Details.	1	EA	\$ 1,500.00	\$ 1,500.00
Subtotal - Category 1			\$ 2,312.50	\$ 2,393.75
02. Site Prep and Demolition				
Site Prep Small to Medium Project (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.	1	EA	\$ 412.95	\$ 454.25
PATIO DOOR: Demolition of work area to EPA lead safe work practices: Demo the existing window, interior and exterior trim, and base molding on that window wall and dispose. Demo the interior wall covering as needed. Make a clean cut in the stucco to demo the stucco directly below the window. Demo the framing as needed to create the new patio door rough opening. NOTE: Although great care is taken and it is almost never an issue, if the stucco chips or if a stucco patch is needed, there will be additional costs. NO stucco work is included in this proposal.	1	EA	\$ 638.40	\$ 702.24
DECK: Demo out (2) 16"X16" holes in the existing concrete patio for two of the new footing holes. Demo stucco as needed across the house for install of the new 2X10 treated ledger board	1	EA	\$ 541.30	\$ 595.43
<i>NOTE: Although care is taken to carefully remove tile from walls and floor occasionally screw pops, hairline cracks, and other issues can arise in adjacent spaces; no costs are included in this estimate to patch drywall or repaint walls in adjacent spaces but the need could arise and can be handled with a Change Order. We also use the most expensive and sensitive tape when taping prep to the floor, walls, or trim. If it is a bad or old finish, there is a small chance that it may peel some of the existing finish off. Any additional repairs will be an additional charge and dealt with in a non-chargeable change order.</i>	1	Note	\$ 0.00	\$ 0.00
Subtotal - Category 2			\$ 1,592.65	\$ 1,751.92
03. Landscaping and Fence - By Field Outdoor Spaces				
Subtotal - Category 3			\$ -	\$ -
04. Concrete and Foundation				
Pier Footings - 8" X42" with 12" bell	2	EA	\$ 633.60	\$ 696.96
Pier Footings - 12" X42" with 18" bell	3	EA	\$ 1,126.35	\$ 1,238.99
Subtotal - Category 4			\$ 1,759.95	\$ 1,935.95
05. Masonry				
Subtotal - Category 5			\$ -	\$ -
06. Framing				

Remove LOAD BEARING wall and frame a new opening. Includes new headers for the support of the weight above. PATIO DOOR: Frame for the new patio door rough opening. To include a new (2) 2X8 header and king studs for the new opening. Install a new treated sill under the new patio door after the wall is removed.	1 EA	\$	978.80	\$	1,076.68
Deck Framing: Frame deck with treated 2X10, 16" O.C.. Includes install of ledger board, rim joist, and header. Includes all needed mechanical fasteners (hangers, etc.) DOES NOT include decking.	241 SF	\$	5,043.29	\$	5,547.62
Deck Stairs: Frame deck stairs with treated 2X12 stair jacks, 12" O.C.. See Category 10 Includes all needed mechanical fasteners (hangers, etc.) DOES NOT include decking or risers.	30 LF	\$	618.42	\$	680.26
Subtotal - Category 6		\$	6,640.51	\$	7,304.56
09. Roofing, Flashing, Gutters					
Subtotal - Category 9		\$	-	\$	-
10. Exterior Trim, Porches and Decks					
Furnish and install Cedar exterior trim (5/4x?)	21 LF	\$	183.94	\$	202.33
Width:					
Furnish and install maintenance free aluminum wrap over wood window or door trim. Count EACH window/door	1 EA	\$	175.00	\$	192.50
Color:					
<u>NOTE: Additional \$100 will be added for a non-standard color</u>					
Decking - 5/4" X 6", Kiln dried, Cedar tone Treated decking with cedar colored top mount screws;	271 SF	\$	5,060.11	\$	5,566.12
Skirting/stair riser - Cedar 1X10 skirting around the perimeter of the framing and stair risers.	76 LF	\$	1,445.37	\$	1,589.90
Railing - Cedar - Includes: 4X4 newel posts, vertical 2X4 top and bottom supports with a 5/4 X 6 top cap. <u>2X2 spindles</u>	57 LF	\$	3,050.41	\$	3,355.45
Remove (2) sections of fence on the south side of the new deck and dispose. Remove the existing gate and SAVE. Remove the section of fence closest to the garage and re work to tie in deck to the existing fence post and fill in next to the new gate location. Dig for a new 4X4 treated post. Wrap with cedar in similar detail of the other posts. Re-install the existing gate and it's hardware.	1 EA	\$	763.40	\$	839.74
Subtotal - Category 10		\$	10,678.23	\$	11,746.05
11. Siding, Soffit, and Fascia					
Subtotal - Category 11		\$	-	\$	-
12. Exterior Doors and Trim					
Furnish and install ultra sliding glass clad/wood patio door; <u>Door allowance: \$1,600.00/set</u> Manufacturer/supplier: Door Size: Operating panel (viewed from exterior): Jamb Depth: Grids: Grid type Hardware Color:	1 EA	\$	3,263.40	\$	3,589.74
Subtotal - Category 12		\$	3,263.40	\$	3,589.74
13. Windows					
Subtotal - Category 13		\$	-	\$	-
14. Plumbing					
Subtotal - Category 14		\$	-	\$	-
15. HVAC					
Subtotal - Category 15		\$	-	\$	-
16. Electrical					
Subtotal - Category 16		\$	0.00	\$	0.00
17. Insulation					
Subtotal - Category 17		\$	-	\$	-
18. Drywall					

Subtotal - Category 18		\$	-	\$	-	
19. Tile and Stone						
Subtotal - Category 19		\$	-	\$	-	
20. Millwork, Doors, Hardware						
Moderate window and door casing - NOTE: Assumes 2 1/4" casing and "picture framed" windows	21 LF	\$	196.76	\$	216.44	
Species:						
Size:						
Profile #:						
"Picture framed" OR sill/stool detail:						
Supplier:						
Subtotal - Category 20		\$	196.76	\$	216.44	
21. Cabinetry, Countertops and Appliances						
Subtotal - Category 21		\$	0.00	\$	0.00	
22. Specialties						
Subtotal - Category 22		\$	-	\$	-	
23. Flooring						
Subtotal - Category 23		\$	-	\$	-	
24. Painting and Decorating						
Finishing of an EXTERIOR door 1 side (interior). Includes the jamb of the unit. <u>NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.</u>	1 EA	\$	382.90	\$	421.19	
Manufacturer:						
Color name and #:						
Sheen: (satin is standard)						
NOTE: Please note that when the homeowner is doing the painting, they are responsible for caulking, filling nail holes, and repairing minor wall and ceiling dings. There will need to be a few rounds of touch-ups, due to the nature of construction, and that falls under the scope of the painter.		1 Note	\$	0.00	\$	0.00
Subtotal - Category 24		\$	382.90	\$	421.19	
25. Clean Up and Debris Removal						
Disposal and clean-up - remove all site prep, wipe down and broom sweep area. Haul all extra material off site.	1 EA	\$	319.20	\$	351.12	
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.	1 MO	\$	80.00	\$	80.00	
<u>NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.</u>						
DUMPSTER NOTE: If the dumpster is placed on the street, and the city calls a snow emergency or street cleaning, there will be an additional \$200 charge per move or violation via a change order. Sometimes it will get moved, sometimes it will just get fined. The charge is the same either way.		0 EA	\$	0.00	\$	0.00
10 Yard mini roll-off dumpster - smaller truck for smaller places 2.5 ton maximum NOTE: for 30 days only. Use line above for estimated days over 30 days	1 EA	\$	337.50	\$	371.25	
Regular portable restroom (one month)	1 EA	\$	212.50	\$	233.75	
<u>NOTE: This cost can be saved if home owner is ok with making a bathroom in the house available to Castle and it's trade partners</u>						
Subtotal - Category 25		\$	949.20	\$	1,036.12	
Project Subtotal		\$	27,796.10	\$	30,395.71	
26. Designer Oversight & Project Management		\$	2,640.63	\$	2,904.69	
27. Overhead and Profit		\$	4,586.36	\$	5,044.99	
Grand Total**		\$	35,023.08	\$	38,525.39	

MN License # BC005657

****Important Notice****

****This is only a ballpark guesstimate. This does not represent actual prices, only a best guess based on Castle's past experiences. There are still many unknowns that can affect pricing at this point.**

Check or Cash Discount Low 2.5%*	\$ 875.58	Check or Cash Discount High 2.5%*	\$ 963.13	\$ 34,147.51	\$ 37,562.26
-------------------------------------	-----------	--------------------------------------	-----------	--------------	--------------

*Doesn't Apply to Bank Financing or loan process that requires Castle to receive payment directly from that entity after Castle has paid subcontractors and secured lien waivers. In these instances Castle essentially acts as

Custom Design Showrooms



5 W. Diamond Lake Rd
Minneapolis, MN 55419
Pj 612-789-8509



2600 Johnson St. NE
Minneapolis, MN 55418
Pj 612-789-8509



362 Snelling Ave S.
St. Paul, MN 55105
Pj 651-699-4164



4020 Minnehaha Ave
Minneapolis, MN 55406
Pj Pj 612-789-8509

Showroom maps & hours can be found on our website at www.CASTLEBRI.com



Need Help with Financing Options?



<https://www.castlebri.com/financing-options/>

Castle Offers Financing

\$ Up to \$25k or 50% of project cost	% 7% interest rate	📅 Up to 60 month term
🔒 Completely unsecured loan	🚫 No fees, closing costs or prepayment penalties	🔄 On approved credit Requires ACH payment

Find out if you qualify Call or email Tandra Heine, Financial Controller at 612.877.8374 or Tandra@castlebri.com to schedule your 10 minute no obligation consultation.