

BUDGET ANALYSIS

Client Information:

Home Office Remodel

Address:

City, State, Zip:

Phone: Email:

Project Description:

Convert an existing 12-by-12 foot room to a home office. Install custom cabinets to include 12 linear feet of laminate desktop, computer workstation and wall cabinet storage. Rewire room for computer and other electronic equipment. Includes drywall of interior, painted trim and upgraded carpeting.

	Qty. Unit Ima	lge Low	Low Budget		High Budget	
L. Permits and Design						
Permit.	1 EA	\$	600.00	\$	660.0	
Design and Planning Process- see Design and Planning Agreement for details.	1 EA	\$	600.00	\$	600.	
btotal - Category 1		\$	1,200.00	\$	1,260.	
2. Site Prep and Demolition						
Site Prep Small to Medium Project: -Tools/equipment delivery and set up of job sitePlace yard sign and order dumpsterFloor protection to work areaPoly curtain walls and zipper doors to work area.	1 EA	\$	648.50	\$	713.	
Demolition of work area: -Demo interior drywall on wall of cabinetry/electrical and flooring down to subfloorRemove and save base/shoe.	1 EA	\$	1,344.00	\$	1,478	
btotal - Category 2		\$	1,992.50	\$	2,191.	
5. Framing						
Basic interior wall framing: -Flatten walls and ceilingFur out as neededFurnish and install backers for rock and accessories.	1 EA	\$	436.00	\$	479.	
btotal - Category 6		\$	436.00	\$	479	
5. Electrical						
Electrical Permit.	1 EA	\$	231.25	\$	254	

Device color: White, light almond, or ivory are standard Switch style: Pole or Decora	1 EA	\$ 0.00	\$	0.00
Finished price for electrical receptacles, cat 5, etc. Does not included sub panel or new electrical pa	1 EA	\$ 1,875.00	\$	2,062.50
Light fixture- CBR furnish and elec install:	1 EA	\$ 340.00	\$	374.00
\$150 allowance			*	
Manufacturer:				
Model:				
Finish:				
Bulb:				
ubtotal - Category 16		\$ 2,446.25	\$	2,690.88
7. Insulation				
ubtotal - Category 17		\$ -	\$	-
8. Drywall				
Walls- 1/2" drywall with smooth finish.	96 SF	\$ 1,224.00	\$	1,346.40
ubtotal - Category 18		\$ 1,224.00	\$	1,346.40
9. Tile and Stone				
ubtotal - Category 19		\$ -	\$	-
0. Millwork, Doors, Hardware				
Base molding - moderate 1 piece shorter base:	24 LF	\$ 589.08	\$	647.99
Manufacturer:				
Model:				
Species:				
Size:				
Location:				
ubtotal - Category 20		\$ 589.08	\$	647.99
1. Cabinetry, Countertops and Appliances				
Knobs and pulls:	10 EA	\$ 200.85	\$	220.94
\$7 allowance				
Manufacturer:				
Model:				
Size- center set:				
Projection:				
Finish:				
Location:	1.54	0.00	Φ.	0.00
CABINET SPECS:	1 EA	\$ 0.00	\$	0.00
Cabinet Line: Crystal Current, Keyline, or Encore				
Box Type: Framed, Inset, or Frameless				
Door Construction: MDF or Wood Door Style:				
Drawer Style: 5 piece or slab				
Drawer box construction:				
Interior material: current- natural melamine on particle board substrate standard or natural				
basswood veneer on plywood substrate upgrade, white melamine on particle board substrate				
available current frameless, all plywood green core box with natural maple veneer available if				
keyline; finished interiors of any cabinets would be noted on plans.				
Wood Species:				
Finish: paint or stain				
Color:				
Sheen:				
Specialties: (distressing, highlights, etc.)				
Specialties: (distressing, highlights, etc.) Crown:				
Crown:				
Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on				
Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished				
Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on drawing, not included. Crystal accessories (location noted on plan):				
Crown: Shoe: Yes Finished end: Furniture groove finished end (standard) or optional upgrade to flush finished Any applied doors or end panels to sides or backs of cabinets will be noted on plans. If not on drawing, not included.				

I n w	C LE	I e	2 100 75	6	2 400 92
Base cabinets: Manufacturer: Crystal Cabinets	6 LF	\$	2,190.75	2	2,409.83
Model: Current or frameless current					
NOTE: see specs above.					
There we also store	6 LF	\$	2,067.60	¢.	2,274.36
Upper cabinets: Manufacturer: Crystal Cabinets	0 LF	\$	2,067.60	\$	2,274.30
Model: Current or frameless current					
NOTE: see specs above.					
Plastic laminate countertops:	24 SF	\$	1,200.00	\$	1,320.00
Manufacturer:	24 51	Ψ	1,200.00	Ψ	1,520.00
Color:					
Thickness:					
Edge Profile:					
Back Splash (Y or N): integrated or set on Front overhang: 1 1/4" from box is standard for framed and frameless, 1" from box is standard	lard for				
inset	aru ioi				
Side overhang: 1" from box is standard					
Subtotal - Category 21		\$	6,083.32	\$	6,691.65
22. Specialties		•	0,000.02	Ψ	0,071.00
Subtotal - Category 22		\$	_	\$	_
		J	-	Ф	<u> </u>
23. Flooring	1 E A	6	50.00	¢.	<i>55</i> 00
Floor transitions: Manufacturer:	1 EA	\$	50.00	\$	55.00
Type: t mold, reducer, etc.					
Finish:					
Locations:					
Carpet and pad- upgraded:	144 SF	\$	1,215.00	\$	1,336.50
\$5.75 allowance					
Manufacturer:					
Line/series: Color:					
Pad:					
Subtotal - Category 23		\$	1,265.00	\$	1,391.50
24. Painting and Decorating					
Ceilings- prime and painting:	144 SF	\$	462.17	\$	508.38
Color: Standard flat ceiling white					
Rooms:					
Walls- prime and paint:	384 SF	\$	681.02	\$	749.13
Manufacturer:					
Color name and #:					
Sheen:					
Rooms:		1.			
Molding (base, casing) - priming and painting: Manufacturer:	48 LF	\$	674.40	\$	741.84
Color name and #:					
Sheen: satin is standard					
Items: base, casing, crown, etc.					
Rooms or locations:					
Subtotal - Category 24		\$	1,817.59	\$	1,999.35
25. Clean Up and Debris Removal					
Disposal and clean-up:	1 EA	\$	146.42	\$	161.06
-Remove all site prep, wipe down and broom sweep area.					
-Haul all extra material off site.					
NOTE: This doesn't include professional cleaning. Deep clean available at additional cost handled on a change order at end of project.	si to be				
6 Yard mini roll-off dumpster:	1 EA	\$	384.84	\$	423.32
-Smaller truck for smaller places.	-		2201	-	.20.02
-2.5 ton maximum.					
NOTE: For 30 days only. See line below for additional months.					
Subtotal - Category 25		\$	531.26	\$	584.38
Project Subtotal		\$	17,585.00	\$	19,283.50
26. Designer Oversight & Project Management		\$	1,846.42	Φ.	2,031.07

27. Overhead and Profit				\$ 2,901.52	\$ 3,191.68		
Grand Total**						\$ 22,332.94	\$ 24,566.24
MN License # BC005657 **Important Notice** **This is only a ballpark guesstimate. This does not represent actual prices, only a best guess based on Castle's past experiences. There are still many unknowns that can affect pricing at this point.							
Check or Cash Discount Low 2.5%*		Check or Cash Discount High 2.5%*	\$	614.16		\$ 21,774.62	\$ 23,952.08

^{*}Doesn't Apply to Bank Financing or loan process that requires Castle to receive payment directly from that entity after Castle has paid subcontractors and secured lien waivers. In these instances Castle essentially acts as the financier for the project and incurs borrowing costs. Exceptions include banks willing to follow Castle payment structure.

Custom Design Showrooms



5 W. Diamond Lake Rd Minneapolis, MN 55419 P) 612-789-8509



2600 Johnson St. NE Minneapolis, MN 55418 P) 612-789-8509



362 Snelling Ave S. St. Paul, MN 55105 P) 651-699-4164

Showroom maps & hours can be found on our website at www.CASTLEBRI.com

Need Help with Financing Options?



HTTPS://WWW.CASTLEBRI.COM/FINANCING-OPTIONS/