

Name:  
 Address:  
 City, State, Zip:  
 Phone:  
 Email:



## BUDGET ANALYSIS

**Project Description:**

**Date:** 2/12/2020

Replace (10) existing 3' by 4' double-hung windows with clad/wood replacement sash kits. New interior stop. Includes interior finishing. Option not included: wrap existing exterior trim with aluminum as required to match.

	Qty.	Unit	Low Budget	High Budget
<b>01. Permits and Design</b>				
Permit	1	EA	\$ 480.00	\$ 528.00
<b>Subtotal - Category 1</b>			<b>\$ 480.00</b>	<b>\$ 528.00</b>
<b>02. Site Prep and Demolition</b>				
Site Prep (Includes floor protection, poly curtain walls, and delivery of tools/equipment and set up of job site). Place yard sign and order dumpster. Protect floors through home to work area. Install poly curtain walls and zipper doors to work area.	1	EA	\$ 426.75	\$ 469.43
<b>OPTION:</b> Furnish and install a Schlage "Camelot" keypad electronic deadbolt. Finish: TBD. <b>ADD: \$110.00</b> <b>NOTE:</b> This is priced at our cost with free install. It is a good alternative to having a lock box on your door and you can use it in the future after your project is complete. There are other options that provide "smart" technology as well for a slightly higher cost. Ask your designer for details.	1	EA	\$ 0.00	\$ 0.00
<b>NOTE:</b> Although care is taken to carefully remove tile from walls and floor occasionally screw pops, hairline cracks, and other issues can arise in adjacent spaces; no costs are included in this estimate to patch drywall or repaint walls in adjacent spaces but the need could arise and can be handled with a Change Order. We also use the most expensive and sensitive tape when taping prep to the floor, walls, or trim. If it is a bad or old finish, there is a small chance that it may peel some of the existing finish off. Any additional repairs will be an additional charge and dealt with in a non-chargeable change order.	1	Note	\$ 0.00	\$ 0.00
<b>Subtotal - Category 2</b>			<b>\$ 426.75</b>	<b>\$ 469.43</b>
<b>03. Landscaping and Fence - By Field Outdoor Spaces</b>				
<b>Subtotal - Category 3</b>			\$ -	\$ -
<b>04. Concrete and Foundation</b>				
<b>Subtotal - Category 4</b>			\$ -	\$ -
<b>05. Masonry</b>				
<b>Subtotal - Category 5</b>			\$ -	\$ -
<b>06. Framing</b>				
<b>Subtotal - Category 6</b>			\$ -	\$ -
<b>09. Roofing, Flashing, Gutters</b>				
<b>Subtotal - Category 9</b>			\$ -	\$ -
<b>10. Exterior Trim, Porches and Decks</b>				
Furnish and install maintenance free aluminum wrap over wood window or door trim. Count EACH window/door. Option not included, add approx. \$2425. <b>Color:</b> <b>NOTE:</b> Additional \$100 will be added for a non-standard color	0	EA	\$ 0.00	\$ 0.00
<b>Subtotal - Category 10</b>			<b>\$ 0.00</b>	<b>\$ 0.00</b>
<b>11. Siding, Soffit, and Fascia</b>				
<b>Subtotal - Category 11</b>			\$ -	\$ -
<b>12. Exterior Doors and Trim</b>				
<b>Subtotal - Category 12</b>			\$ -	\$ -

<b>13. Windows</b>					
Furnish and install new custom clad/wood replacement window sash kit.		10 EA	\$	8,226.25	\$ 9,048.88
<b>Subtotal - Category 13</b>				<b>\$ 8,226.25</b>	<b>\$ 9,048.88</b>
<b>14. Plumbing</b>					
<b>Subtotal - Category 14</b>				<b>\$ 0.00</b>	<b>\$ 0.00</b>
<b>15. HVAC</b>					
<b>Subtotal - Category 15</b>				<b>\$ -</b>	<b>\$ -</b>
<b>16. Electrical</b>					
<b>Subtotal - Category 16</b>				<b>\$ 0.00</b>	<b>\$ 0.00</b>
<b>17. Insulation</b>					
<b>Subtotal - Category 17</b>				<b>\$ -</b>	<b>\$ -</b>
<b>18. Drywall</b>					
<b>Subtotal - Category 18</b>				<b>\$ -</b>	<b>\$ -</b>
<b>19. Tile and Stone</b>					
<b>Subtotal - Category 19</b>				<b>\$ -</b>	<b>\$ -</b>
<b>20. Millwork, Doors, Hardware</b>					
Window stop -		140 LF	\$	544.95	\$ 599.45
Species:					
Supplier:					
<b>Subtotal - Category 20</b>				<b>\$ 544.95</b>	<b>\$ 599.45</b>
<b>21. Cabinetry, Countertops and Appliances</b>					
<b>Subtotal - Category 21</b>				<b>\$ 0.00</b>	<b>\$ 0.00</b>
<b>22. Specialties</b>					
<b>Subtotal - Category 22</b>				<b>\$ -</b>	<b>\$ -</b>
<b>23. Flooring</b>					
<b>Subtotal - Category 23</b>				<b>\$ -</b>	<b>\$ -</b>
<b>24. Painting and Decorating</b>					
Priming and painting on interior side of window, <b>one side</b> . <u>NOTE: Our standard is low VOC for woodwork, although may not be able to use low VOC primer due to existing stain/wood condition- tbd. Will use low VOC primer when able.</u>		10 EA	\$	2,810.00	\$ 3,091.00
Manufacturer:					
Color name and #:					
Sheen: (satin is standard)					
<b>NOTE: Please note that when the homeowner is doing the painting, they are responsible for caulking, filling nail holes, and repairing minor wall and ceiling dings. There will need to be a few rounds of touch-ups, due to the nature of construction, and that falls under the scope of the painter.</b>		1 Note	\$	0.00	\$ 0.00
<b>Subtotal - Category 24</b>				<b>\$ 2,810.00</b>	<b>\$ 3,091.00</b>
<b>25. Clean Up and Debris Removal</b>					
Disposal and clean-up - remove all site prep, wipe down and broom sweep area. Haul all extra material off site.		1 EA	\$	333.00	\$ 366.30
Minneapolis daily street use permit for dumpster - Charged per 30 days. If dumpster can be placed on driveway or lawn this can cost can be saved.		1 MO	\$	80.00	\$ 80.00
<u>NOTE: If the dumpster is required to be moved for plowing or street cleaning, there will be additional charges for moving it and replacing it after the street work is complete.</u>					
<b>DUMPSTER NOTE: If the dumpster is placed on the street, and the city calls a snow emergency or street cleaning, there will be an additional \$200 charge via a change order. Sometimes it will get moved, sometimes it will just get fined. The charge is the same either way.</b>		0 EA	\$	0.00	\$ 0.00

6 Yard mini roll-off dumpster - smaller truck for smaller places 2.5 ton maximum. <b>NOTE:</b> for 30 days only. Use line above for estimated days over 30 days	1 EA	\$	256.25	\$	281.88
<b>Subtotal - Category 25</b>		\$	<b>669.25</b>	\$	<b>728.18</b>
<b>Project Subtotal</b>		\$	<b>13,177.20</b>	\$	<b>14,464.92</b>
<b>26. Project Management</b>		\$	1,054.18	\$	1,159.59
<b>27. Administrative Fees and Sales Tax Paid on Material Purchases</b>		\$	329.43	\$	362.37
<b>28. Designer Oversight</b>		\$	197.66	\$	217.42
<b>29. Overhead and Profit</b>		\$	1,844.81	\$	2,029.29
<b>Grand Total**</b>		\$	16,603.27	\$	18,263.60

MN License # BC005657

**\*\*Important Notice\*\***

**\*\*This is only a ballpark guesstimate. This does not represent actual prices, only a best guess based on Castle's past experiences. There are still many unknowns that can affect pricing at this point.**

<b>Check or Cash Discount Low 2.5%*</b>	\$	<b>415.08</b>	<b>Check or Cash Discount High 2.5%*</b>	\$	<b>456.59</b>	\$	<b>16,188.19</b>	\$	<b>17,807.01</b>
---	----	---------------	--	----	---------------	----	------------------	----	------------------

\*Doesn't Apply to Bank Financing or loan process that requires Castle to receive payment directly from that entity after Castle has paid subcontractors and secured lien waivers. In these instances Castle essentially acts as the financier for the project and incurs borrowing costs. Exceptions include banks willing to follow Castle payment structure.

**Custom Design Showrooms**



5 W. Diamond Lake Rd  
Minneapolis, MN 55419  
P) 612-789-8509



2600 Johnson St. NE  
Minneapolis, MN 55418  
P) 612-789-8509




362 Snelling Ave S.  
St. Paul, MN 55105  
P) 651-699-4164



4020 Minnehaha Ave  
Minneapolis, MN 55406  
P) 612-789-8509

Showroom maps & hours can be found on our website at [www.CASTLEBRI.com](http://www.CASTLEBRI.com)



*Need Help with Financing Options?*



<https://www.castlebri.com/financing-options/>